

REPORT of SURVEY for REPAIRS, &c.

No. 41642 (Received at London Tuesday, 25th July, 1882)

No. in Survey held at London Date, first Survey June 26 Last Survey July 19th 188 2

Reg. Book. 1250 on the SS Aurora (No. of Visits 5) Master Chenoweth

TONNAGE under Tonnage Deck 646 Built at Newcastle When built 1863 YEAR. MONTH.

Ditto of Spar Deck, or Avoing Deck 711 Owners Sen Shu Ship Co Port belonging to London

Ditto of Poop 711 Residence Palmer Destined Voyage Mediterranean

Ditto of Raised Qr. Dk. 711 By whom built Palmer If Surveyed Afloat or in Dry Dock Pontoon & Victoria St

Ditto of Houses on Deck 711 (State Name of Dock)

Ditto of Forecastle 711 Gross Tonnage 711 Years assigned. Character in Register Book.

Crew Space, as per Rule 711 Register Tonnage, cut on Beam 711 Engine Room 711 Reg. Tons as St' mer, cut on Bm. 446

Length of Poop ft. Ditto, Forecastle ft. Ditto, Raised Quarter Deck ft.

Last Survey, No. 40750 Port London Classed 95 A 1 8.81

REPAIRS, OR EXAMINATION AS PER RULE P. P. do. 3-72 SS Sen W 280.

Cause of Repairs to be clearly stated.

At the present time the Coal Bunkers cleared and the Oxidation shipped and beaten off & examined Repairs Starboardside Coal Bunker. 5 Frames & 6 Reversed Frames shifted and well butt strapped. 2 doubling Plates on Poop Stinger. A new Stinger overlapping Main Deck Stinger & running into Coal Bunker (Raised Quarter Deck) about 14 feet & the same on opposite side of ship. Port new Stinger below & all rivetted & the same on Portside Portside in Coal Bunker 6 Frames & 5 Reversed Frames shifted & well butt strapped. Many Rivets in shell plating & frame renewed on both sides. Holes also drilled in the plating & found in good condition 10 Poop Deck Planks on both sides renewed with Yellow Pine

Present Condition of the

Decks	Good	Treenails	Rivets	Good	Windlass and Capstan	Good
Waterways	"	Breasthooks and Stemson	"	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	"	Condition, how ascertained	From St
Planksheers	"	Keelsons	"	"	Sails	Good
Sheerstrakes	"	Clamps and Shells	"	"	Anchors No. of 3 No. 12 & 16 Ropes	"
Topsides	"	Ceiling	"	"	Cables Port & St	Good
Wales	"	Rudder	"	"	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper (or r.m.) Coated When put on	Now	"	Standing & Running Rigging	"
Engine Room Skylights	Good	Caulking of Bottom, Deck, & Waterways	Good	"		
Coal Bunker, Openings, Lids, &c.	Good			"		
Scuppers	Good			"		
Cargo and Main Hatchways	Good			"		
Hatches	"			"		

General Observations, Opinion as to Class, &c.

She is now in an efficient state and eligible to remain as classed.

The Amount of Entry Fee ... £ 4 : 4 : received by me, 448

Certificate (if required) to be sent as per margin... £ : :

(Travelling Expenses, if any, £)

Committee's Minute

Friday, 25th July, 1882.

Character assigned

B-3-7-82

ROBT. EDM. TAYLOR & SON, Commercial Steam Printers, 19, Old Street Goswell Road, London.

Senhouse Martindale
Surveyor to Lloyd's Register of British and Foreign Shipping.



© 2021

Lloyd's Register Foundation

LONG68-0457