

Report of Survey for Repairs of Engines and Boilers.

No. 58 on the Machinery of the S. S. James Joyce (Number of Visits 2)
 (Received at London Office, 3.5.82)
 No. in Reg. Book. 58 Survey held at London Date, first Survey 30 June Last Survey 1st July 1882.
 Tonnage, Gross 702 Built at Newcastle When built 1863
 Ditto, Net 441 Owners J. Fenwick & Son Port belonging to London
 Diameter of Cylinder 38" Engines made by R & N. Hawthorn When made 1863
 Length of Stroke 30" Boilers made by 1873
 Pressure of Steam 33 lbs. If Surveyed Afloat or in Dry Dock Pontoon (State name of Dock.)
 Registered Horse Power 90 Classed A 1
 Last Survey No. 90 Port M.S. 9.79. B.S. 6.81.

Particulars of Repairs and Examination For Special Survey No. 1.

(State cause of Repairs.)

Vessel placed on Pontoon, sea connections examined & found to be in good condition. Propeller & its connections found to be sound & the tail shaft down to in Stern bush. This is a solid brass bush without lignum vitae strips. Boilers examined, a piece about 9' deep has been cut out of back of combustion chamber of wing furnace in Port Boiler & new stays fitted, with this exception the remainder of boilers were found to be in good condition. Safety Valves examined & found " " A new Crank shaft has been fitted. Examined cylinders Slides & Valve Faces, in good condition. Air Circulating Pumps. " " " Fuel & Bilge Pumps & Valves. " " "

General Observations, Opinion, and Recommendation:— The machinery being now in good & safe working condition under the vessel eligible in my opinion to be marked in the Register Book with L. M. C. 7. 82. Provided that the boilers are again examined within 12 mths. as per rule.

Entry or Registering Fee... £ 1 : : :
 Survey Fee (per Section 27.)... £ 2 : 2 : } received by me,
 Certificate (if required) ... £ - : - : } 18 Aug 1882
 to be sent as per margin.
 (Travelling Expenses, if any, £)

Committee's Minute

Assigned

Friday, 4th August, 1882,

Geo. E. Milnerison.
 Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



Lloyd's Register
 Foundation

L04663-0504

He submitted that the vessel
is eligible to have the
notification S.M.C. 7.82
recorded the boilers
being subject to Annual
Survey as per Rule

PM 2/8/82



© 2021

Lloyd's Register
Foundation