

Report of Survey for Repairs of Engines and Boilers.

(Received at London Office, 31/8/82)


No. _____
 No. in Reg. Book. *411* Survey held at *London* Date, first Survey *19 Aug* Last Survey *28 Aug 1882*
 on the Machinery of the *S. J. Dublin Castle* (Number of Visits *4*)
 Tonnage, Gross *2911* Built at *Glasgow* When built *1877*
 Ditto, Net *1856* Owners *D. Currie & Co* Port belonging to *London*
 Diameter of Cylinder *47* *75* Engines made by *R. Napier & Sons* When made *1877*
 Length of Stroke *48* Boilers made by _____ When made *1877*
 Pressure of Steam *60* If Surveyed Afloat or in Dry Dock *Green Dry Dock & East India Dock* Years assigned *100 A1*
 Registered Horse Power *300* (State name of Dock.) *6.82* Character in Register Book. *L. M. C. 10.81.*
 Last Survey No. _____ Port _____

Particulars of Repairs and Examination *Change of Owners.*
 (State cause of Repairs.)
Examined Siacocks & connections & found them in good condition
Examined Propeller & found several cracks in root of one blade, this has been replaced by a new one.
Examined two double ended boilers & superheater found them in a good condition. Several furnaces have double bottoms, others are patched on account of pitting. The Superheater is in a good condition.
Examined Safety valves, slide valves & chambers, cylinders pumps & condenser & found them in a good condition
Examined Lammel and crankshaft & found them in a good condition
The safety valves blow off at 60 lbs.

General Observations, Opinion, and Recommendation:— *The machinery of this vessel appears to be in a safe & efficient working condition and ~~is~~ in my opinion eligible to have the notification L. M. C. 8. 82 recorded in the Register Book.*

Entry or Registering Fee... £ *1.18*
 Survey Fee (per Section 28) ... £ *4.4*
 Certificate (if required) ... £ *3*
 (The Surveyors are requested not to write on or below the space for Committee's Minute.)
 Committee's Minute *31st August 1882*
 Assigned *L. M. C. 10.81*

C. J. Browley
 Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



(Stat. if Report is also sent or. etc.)
 (Condition of Engines and Boilers, and subsequent Repairs and Examinations, to be clearly stated.)
 (The Surveyors are requested not to write on or below the space for Committee's Minute.)

(Insert Character precisely as in the Register Book.)

It is submitted that this
asset is eligible to have
the notification SMC. 8.82
recorded. The bodies
being subject to Annual
Survey as per Rule

M 31/8/82



© 2021

Lloyd's Register
Foundation