

# Report of Survey for Repairs of Engines and Boilers.

No. \_\_\_\_\_ (Received at London Office, \_\_\_\_\_)  
No. in Reg. Book. Survey held at London Date, first Survey 18 Oct Last Survey 24 Oct 1882  
753 on the Machinery of the S. J. Ann Webster (Number of Visits 3)  
Tonnage, Gross 771 Built at Hartlepool When built 1870  
Ditto, Net 498 Owners Commercial Steam Ship Port belonging to London  
Diameter of Cylinder 25 48 Engines made by Richardson & Sons When made 1870  
Length of Stroke 36 Boilers made by \_\_\_\_\_ When made 1880  
Pressure of Steam 75  
Registered Horse Power 96  
If Surveyed Afloat or in Dry Dock Limekiln Dock Years assigned 90 A1  
(State name of Dock.) & River Character in Register Book. 10-81  
Last Survey No. \_\_\_\_\_ Port \_\_\_\_\_ B & M.S. 1280

Particulars of Repairs and Examination Special Survey No 1.  
(State cause of Repairs.)

Examined Leacocks & connections & found them in good condition

New Lignum vice has been fitted & the tailshaft examined.

Examined Boilers and found them to be in a good condition  
a few stays have been renewed & patches fitted.

Examined Safety valves, Slide valves, cylinders, crankshaft  
pumps and found them to be in a good condition

The Safety valves blew off at 71 lbs pressure

General Observations, Opinion, and Recommendation:— The machinery of this vessel appears to be in a safe working condition and  
is in my opinion eligible to have the notification B &  
M.S. 10-82 recorded in the Register Book.


Entry or Registering Fee... £ 1 : 0 : 0  
(per Section 27.)  
Survey Fee (per Section 28) ... £ 4 : 4 : 0  
Certificate (if required) ... £ - : 2 : 6  
to be sent as per margin.  
(Travelling Expenses, if any, £ \_\_\_\_\_)

received by me,  
9th Nov 1882

Committee's Minute Friday, 3rd November 1882

Assigned

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



Lloyd's Register  
Foundation

LON 669-0195



