

Report of Survey for Repairs of Engines and Boilers.

42204

in Survey held at London

(Received at London Office, 2/2/83)

Date, first Survey Jan. 26th Last Survey Jan. 31st 1883.

on the Machinery of the S. S. "Slaperayder"

(Number of Visits 5)

Displacement, Gross 233

Built at Renfrew

When built 1866

Ditto, Net 155

Owners H. C. Chusuright

Port belonging to London

Diameter of Cylinder 22"

Engines made by Henderson Colburn & Co.

When made 1866

Length of Stroke 22"

Boilers made by Ditto

When made 1878

Pressure of Steam 34 lbs.

Registered Horse Power 40

If Surveyed Afloat or in Dry Dock Nelson D. Dock

(State name of Dock.)

Classed

Character in Register Book.

B 1

Last Survey No.

Port

B + M. S. 7. 79.

Particulars of Repairs and Examination According to the requirements for
(State cause of Repairs.) Special Survey No 2.

Vessel placed in dry dock sea connections examined
found to be in good condition. Propeller disconnected
Tail shaft examined, found in good condition, new
brass bush fitted in Stern tube & propeller replaced.
Examined cylinders, Slide valves, faces & Pistons.
" Crank & Thrust Bearing
" Air, circulating Feed & Bilge Pumps.
" Main Boiler & Safety Valves.

All found in good condition. Safety Valves loaded
to 34 lbs per sq. in. Donkey boiler examined in good
condition, loaded with a lever spring balance,
recommended a brass tube to be hazed on so that lever
could not be screwed down beyond 34 lbs. which has
been done

General Observations, Opinion, and Recommendation:— The machinery being
now in good & safe working condition renders the
vessel eligible in my opinion to be marked with
B + M. S. 7. 83

or Registering Fee... £ : 10 : 0

Fee (per Section 28) ... £ : 3 : 0

Certificate (if required) ... £ : 2 : 0

ing Expenses, if any, £

received by me, 77.8
23/5 1883

Geo. J. Wilkinson
Engineer, Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute

Friday, 9th February, 1883.

Assigned

B + M. S. 1, 83

102669-0585

It is submitted that this vessel is eligible
to have the notification B.M.S. 1.83 provided
subject to the boiler being surveyed in
12 months as per Rule.

DG
1/2/83



© 2021

Lloyd's Register
Foundation