

ation, Ketchikan cut out from between the floors and renewed the
 Cement where necessary, - about 100 strengthening or doubling
 pieces fitted on each side on the Reverse frames where I
 wasted at the Bilges, doubling pieces fitted to 2 frames for
 ward and painting beams strengthened, one frame on Star
 amidships doubled in way of wasted part, - Rudder bush
 Renewed about 3868 feet of Ceiling with 2 1/2 inch Pitch Pine
 also about 675 feet of 2 inch abode, - Topsides Caulked
 from Copper line upwards and about 300 sheets of
 Yellow Metal renewed where planks were removed and the
 Caulking of bottom tested. The Chain Cables ranged and
 found 300 fathoms, the Masts Spars and Windlass examined
 and with the Anchors and general equipment attended
 to. -

The Greenboard Marks as assigned by the Committee put on.

J. W. Miles
 Wm. L. Dancy

Tree in Salt water 3 feet - 9 in
 " " fresh — 8 ft - 5 in

Moulded depth 20 feet 3 in
 per Rept No 148