

Report of Survey for Repairs of Engines and Boilers.

42631
SATURDAY 2 JUNE 1883

(Received at London Office)

No.

No. in
Reg. Book.

Survey held at *London*

Date, first Survey *May 9th* Last Survey *May 28th* 1883

276

on the Machinery of the *S.S. "Rhône"*

(Number of Visits *3*)

Tonnage, Gross *1343*

Built at *Sunderland*

When built *1868*

Ditto, Net *868*

Owners *Muscott & Lawrence*

Port belonging to *London*

Diameter of Cylinder *30 + 54*

Engines ^{comp.} made by *Mull. & Co. Eng. Wks.*

When made *1871*

Length of Stroke *34*

Boilers made by *Ditto*

When made *1871*

Pressure of Steam *55 lbs.*

If Surveyed Afloat or in Dry Dock
(State name of Dock.)

Classed *90A1*

Registered Horse Power *200*

P.F. do 3-82 5-82

Last Survey No. *41455*

Port *London*

B.M.S. 5.82.

Particulars of Repairs and Examination For Annual Survey.

(State cause of Repairs.)

Vessel placed in dry dock sea connections examined
found to be in good condition. Propeller & its connections
round, tail shaft down 4". Boilers examined, pucis cut
out at sides of furnaces in way of bridges. Friction patches
fitted, stays in fairly good condition, sheets fairly good.
Safety valves examined, levers unprotected, recommended
them to be covered in which has been done. Valves loaded
to 55 lbs. per sq. in.

General Observations, Opinion, and Recommendation:— The Boilers being now
in good & safe working condition & the machinery as far
as run, the vessel is eligible in my opinion to remain as
classed than the notification B. S. 5. 83. recorded
provided that the boiler be again examined within
12 mths. on account of its age & condition.

Entry or Registering Fee, £ *1/7/0*

Survey Fee (per Section 28) ... £ *1/1/0*

Certificate (if required)
to be sent as per margin.

(Travelling Expenses, if any, £)

received by me,

10th July 1883

Geo. C. Milnerison.

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

FRIDAY 6 JULY 1883 188

Committee's Minute

Assigned

B. S. 5, 83



© 2021

Lloyd's Register
Foundation

LONB70.0442

(State of repairs, and subsequent repairs and examinations, to be clearly stated.)

(Condition)

(Form No. 9-3000, 1/11/81.)

(The Surveyors are requested not to write on or below the space for Committee's Minute.)

(Insert Character precisely as in the Register Book.)

It is submitted that this vessel is
eligible to have the notification
BS 5.83 recorded the boiler being
renewed for 12 months

M. 1/6/83



© 2021

Lloyd's Register
Foundation