

Report of Survey for Repairs of Engines and Boilers.

No. 386 on the Machinery of the S.S. "Joseph Rickett" (Number of Visits 5)
 Date, first Survey June 25th Last Survey July 7th 1883.

Tonnage, Gross 717 Built at Kinghorn When built 1879
 Ditto, Net 449 Owners Gammon Son & Carter Port belonging to London
 Diameter of Cylinder 24" & 46" Engines made by J. Key & Sons When made 1879
 Length of Stroke 33" Boilers made by Do. When made 1879
 Pressure of Steam 80 lbs. If Surveyed Afloat or in Dry Dock Union S. Dock (State name of Dock.)
 Registered Horse Power 90 Years assigned 90A1 Character in Register Book.
 Last Survey No. T. M. C. 679 Port T. M. C. 679

Particulars of Repairs and Examination In Special Survey No. 1.

Vessel placed in dry dock, sea connections examined & found to be in good condition. Propeller disconnected to run up stern bush, found to be a bad fit on shaft the shaft has had a new end fitted, the hole in propeller cleaned out & shaft properly fitted. Examined cylinders, Slides, Air circulating feed & bilge pumps, crank tunnel shafting, all found to be in good condition, loose brass liners fitted in thrust bearing. Boiler examined found to be in good condition Safety Valves found to be in good condition & set under steam to the working pressure of 80 lbs per sq. in.

General Observations, Opinion, and Recommendation:— The machinery being now in good & safe working condition, renders the vessel eligible in my opinion to be marked in the Register Book with T. M. C. 7. 83., provided that the boiler is again examined within 2 yrs: as per rule.

Entry or Registering Fee... £ — : — :
 Survey Fee (per Section 28)... £ 3 : 3 : — received by me, 27 July 1883
 Certificate (if required) ... £ — : — :
 to be sent as per margin.
 (Travelling Expenses, if any, £)

Geo. E. Milnerison
 Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute

TUESDAY 17 JULY 1883

Assigned



Lloyd's Register
 Foundation
 LON 676 0489

It is submitted that this vessel is
eligible to have the notification
L.M.B. 743 recorded. Subject to
the revision of rules as per Rule

W &

9/7/83



© 2021

Lloyd's Register
Foundation

Boilers of Lloyds for Boilers of Engines and Boilers