

# Report of Survey for Repairs of Engines and Boilers.

43276

No. \_\_\_\_\_ (Received at London Office, FRIDAY 21 DEC 1883)

No. in Reg. Book. Survey held at London Date, first Survey 19 Nov. Last Survey 3 Dec 1883

43 on the Machinery of the S. S. "Hankow" (Number of Visits 6)

Tonnage, Gross 3594 Built at Newcastle When built 1873

Ditto, Net 2332 Owners W. Milburn & Co Port belonging to London

Diameter of Cylinder 52 96 Engines made by R & W Hawthorn When made 1873

Length of Stroke 36 Boilers made by \_\_\_\_\_ When made 1873

Pressure of Steam 63 If Surveyed Afloat or in Dry Dock James Iron Works Years assigned 100A1

Registered Horse Power 450 (State name of Dock.) Classed 3.82

Last Survey No. \_\_\_\_\_ Port L.M.C. 3.82.

Particulars of Repairs and Examination Annual Boiler Survey  
(State cause of Repairs.)  
& Repairs to Boiler

Examined Sea-cocks & connections & found them good. The propeller has been taken off & refitted.

Examined Double ended boilers & Superheater Found Superheater in a good condition

The furnaces of the boilers were severely pitted and have been extensively repaired & patched. The backs of the combustion chambers were cracked in many places & have been patched. Holes were drilled in the furnaces & combustion chambers & the thicknesses of the unrepaired parts were found to be satisfactory.

The Safety valves were found to blow off at 56 lbs.

General Observations, Opinion, and Recommendation:— The boilers of this vessel are now in a safe working condition & she is in my opinion eligible to have the notification B.S. 1283 recorded in the Register Book.

Entry or Registering Fee... £ : :  
(per Section 27.)

Survey Fee (per Section 28) 24/83 £ 2 : 2 — received by me, H. J. Brown

Certificate (if required) £ : : 5.2 1887

(Travelling Expenses, if any, £ )

Committee's Minute \_\_\_\_\_ 188

Assigned B.S. 12, 83

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



Lloyd's Register Foundation



It is submitted that this vessel is  
eligible to have the notification  
BS 12. 83 recorded Subject to the  
resurvey of boilers as per Rule

D.P.  
20/12/83.



© 2021

Lloyd's Register  
Foundation

Report of Survey for Repairs of Engines and Boilers