

Report of Survey for Repairs of Engines and Boilers.

43541

No. _____ (Received at London Office) **FRIDAY 23 FEB 1884**

No. in Reg. Book. *966* Survey held at *London* Date, first Survey *4th Feb^y* Last Survey *21st Feb^y 1884*

on the Machinery of the *S.S. "Stelling"* (Number of Visits *5*)

Tonnage, Gross <i>889</i>	Built at <i>Newcastle</i>	When built <i>1876</i>
Ditto, Net <i>556</i>	Owners <i>J. Fenwick & Son</i>	Port belonging to <i>London</i>
Diameter of Cylinder <i>26.51</i>	Engines made by <i>Palmer's Co.</i>	When made <i>1876</i>
Length of Stroke <i>33</i>	Boilers made by <i>Do.</i>	When made <i>1876</i>
Pressure of Steam <i>75</i>	If Surveyed Afloat or in Dry Dock <i>Victoria Pontoon Dock</i>	Years assigned. <i>90 A1</i>
Registered Horse Power <i>100</i>	(State name of Dock.)	Character in Register Book. <i>11.53</i>
Last Survey No. _____	Port _____	<i>Lm b 10.79</i>

Particulars of Repairs and Examination of machinery Boilers in accordance with the Rules for S.S. No. 1

Examined the cylinders, slides, pistons, pumps and crank shaft found them in fair condition; New crown connecting rod brasses new suction & delivery ^{pipe} to bilge pump fitted

Exam^d the boilers and safety valves, New patch fitted on crown of starboard furnace & patch on combustion chamber of wing port furnace caulked & made tight

Propeller & sea connection examined & found satisfactory

General Observations, Opinion, and Recommendation:— The machinery & Boilers of this vessel are now in good order and safe working condition and eligible in my opinion to have the notification Lm b 284 recorded subject to the resurvey of boilers in 12 months as per Rule


Entry or Registering Fee... £ — : — :
 Survey Fee (per Section 28) ... £ 3 : 3 : 0 } received by me, *7.7.8*
 Certificate (if required) ... £ : : } *6/3* 1884
 to be sent as per margin.

(Travelling Expenses, if any, £ _____)

Committee's Minute **TUESDAY 4 MARCH 1884 188**

Assigned *L. M. b 284*

David Purves
 Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



Lloyd's Register
 Foundation

LON672-0185