

# Report of Survey for Repairs of Engines and Boilers.

(Received at London Office) FRIDAY 14 MARCH 1884

No. 827 on the Machinery of the S.S. "Midsurrey" (Number of Visits 7 Year 1884)

No. in Reg. Book. 827 Survey held at London Date, first Survey Jan. 7<sup>th</sup> Last Survey 4<sup>th</sup> March 1884

Tonnage, Gross 903 Built at Newcastle When built 1870

Ditto, Net 566 Owners Harris & Dixon Port belonging to London

Diameter of Cylinder 25" & 50" Engines made by Palmers Co. When made 18 Year

Length of Stroke 33" Boilers made by Robert Stephenson & Co. When made 18 Year

Pressure of Steam 70 lbs. If Surveyed Afloat or in Dry Dock Summit Hill, D. D.R. & Co. Character in Register Book. 90A1

Registered Horse Power 99 (State name of Dock.)

Last Survey No. 12M.C. 3.79 Port London

## Particulars of Repairs and Examination For Special Survey No. 1.

(State cause of Repairs.)

Vessel placed in dry dock sea connections examined & found to be in good condition. Propeller disconnected tail shaft drawn in & examined, found to be corroded between the brass sleeves, but not sufficiently to renew same, the stern bush has been renewed & propeller refitted. Boilers examined found in good condition with the exception of 18 small stays at base of combustion chambers, these have been renewed. Examined Air, circulating Feed & Bilge pumps cylinders & slides all found to be in good condition. Crank Shaft examined on the 7<sup>th</sup> March 1884 at Wallingford Staiths on the Tyne, and found in a satisfactory condition, adjusted. Safety valves to 70 lbs W.P. Strokehold pressure gauge 10 lbs light recommended it to be adjusted.

General Observations, Opinion, and Recommendation:— The machinery of this vessel is for now in good order and safe working condition and eligible in my opinion to have the notation L M C 3-84 in the Society's Register Book.

Entry or Registering Fee... £ — : — : —  
 Survey Fee (per Section 28) ... £ 3 : 3 : — received by me, J. F. C. Buchanan & Co. & Harrison  
 Certificate (if required) ... £ : : :  
 (Travelling Expenses, if any, £ )

Committee's Minute 188

Assigned L M C 3.79

TUESDAY 13 MARCH 1884

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.





It is submitted that this vessel  
is eligible to have the notification  
L.M.B. 1384 recorded subject to  
the survey of boilers as per  
Rule .

D.F.

12/3/84



© 2021

Lloyd's Register  
Foundation