

Report of Survey for Repairs of Engines and Boilers.

43589

WEDNESDAY 10 MARCH 1884

No. 287 Survey held at London Date, first Survey 24 Jan'y Last Survey 10 March 188

on the Machinery of the S. S. Thornborough (Number of Visits 4)

Tonnage, Gross 739 Built at Newcastle When built 1876

Ditto, Net 463 Owners J. Fenwick & Son Port belonging to London

Diameter of Cylinder 24 45 Engines made by Palmer When made 1876

Length of Stroke 30 Boilers made by Palmer When made 1876

Pressure of Steam 75 If Surveyed Afloat or in Dry Dock Pontoon Years assigned 90 Character in Register Book A1

Registered Horse Power 80 (State name of Dock.) Pontoon Classed 11.83

Last Survey No. L.M.C. 280 Port 188 11.83

Particulars of Repairs and Examination Special Survey and new

donkey boiler

Examined Seacocks & connections & found them good.

Examined Safety valves slide valves cylinders & pumps & found them good

Examined Crankshaft and found an old crack in aft pin about 5 or 6" long & a very small one in the forward crank pin. They are at present of no consequence. The journals were in a good condition.

A new donkey boiler has been fitted on board to replace a smaller one (see attached Report).

The donkey boiler valve was set to 80 lbs. & the main boiler valves were found to blow at 75 lbs.

Examined the main boilers & superheater and found them in a good condition.

General Observations, Opinion, and Recommendation:— The machinery of this vessel appears to be in a safe working condition and is in my opinion eligible to have the notification L.M.C. 3. 84 recorded in the Register Book.

Entry or Registering Fee... £ — : — : —
Survey Fee (per Section 28) 2/6 £ 3 : 3 : — received by me, C. E. Bromley
Certificate (if required) ... £ " : " : " 1884
Travelling Expenses, if any, £

Committee's Minute Friday 21 March 1884 188

Assigned L.M.C. 3. 84

C. E. Bromley
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.
Lloyd's Register Foundation

LON 672-0242

It is submitted that this vessel
is eligible to have the notification
S.M. 63.84 recorded Subject to the
resurvey of boiler as per Rule

DJ

17/3/84.

Report of Survey for Engines and Boilers



© 2021

Lloyd's Register
Foundation