

436 4/4

Report of Survey for Repairs of Engines and Boilers.

No. _____ (Received at London Office, 10. 4. 84.)

No. in Reg. Book. Survey held at London Date, first Survey Mar: 19th Last Survey Apr: 9th 1884

37 on the Machinery of the S. S. "Falcon" (Number of Visits 4)

Tonnage, Gross <u>651</u>	Built at <u>Newcastle</u>	When built <u>1876</u>
Ditto, Net <u>352</u>	Owners <u>Gen. Str. Nav. Co.</u>	Port belonging to <u>London</u>
Diameter of Cylinder <u>30" + 56"</u>	Engines made by <u>Thompson & Co.</u>	When made <u>1876</u>
Length of Stroke <u>33"</u>	Boilers made by <u>Do.</u>	When made <u>1876</u>
Pressure of Steam <u>65 lbs.</u>	If Surveyed Afloat or in Dry Dock <u>L.S.N. Co's D. Dock</u>	Classed <u>100A1</u>
Registered Horse Power <u>130</u>	(State name of Dock.)	
Last Survey No. _____	Port <u>L.M.C. 4. 80.</u>	

Particulars of Repairs and Examination For Special Survey No 2.

(State cause of Repairs.)

Vessel placed in dry dock sea connections examined & found to be in good condition. Propeller disconnected, tail shaft drawn in, examined, found to be in good condition, stern bush renewed & propeller replaced. Examined cylinders slides, Air, Circulating Feed & Bilge pumps & valves & pumping arrangements all found to be in good condition. Crank shaft examined " " " " Thrust shaft " " " " New brasses have been fitted. Boilers examined, furnaces & combustion chambers in good condition, stays in good condition, the lower part of shells have had large brass patches fitted on all the seams at some former time, they are all tight covering plates found fitted to fronts at all four corners. Safety valves examined found in good condition, & set to the working pressure of 65 lbs. per sq. in under steam.

General Observations, Opinion, and Recommendation:— The machinery being now in good & safe working condition renders the vessel eligible in my opinion to be marked in the Register Book with L.M.C. 4. 84 provided that the boilers are again examined within 12 mths. as per rule.

Entry or Registering Fee... £ — : — : —

Survey Fee (per Section 28) ... £ 3 : 3 : — received by me, Geo. E. Milnerison

Certificate (if required) ... £ : : 1. 5. 1886

(Travelling Expenses, if any, £ _____)

Committee's Minute TUESDAY 15 APRIL 1884 188

Assigned M. G. M.



LON 672-0345

Submitted that this vessel is
eligible to have Lloyd's M.C.
4.84 provided the Boilers
are again seen within
12 months.

MM
10.4.84



© 2021

Lloyd's Register
Foundation