

Report of Survey for Repairs of Engines and Boilers.

No.

No. in Reg. Book.

Survey held at

London

Date, first Survey

Mar. 25th

Last Survey

Apr. 8th

1884

663

on the Machinery of the

S. S. "Erasmus Wilson"

(Number of Visits

6

)

Tonnage, Gross

805

Built at

Hartlepool

When built

1876

Ditto, Net

497

Owners

S. Clarke & Co.

Port belonging to

London

Diameter of Cylinder

27 + 50 1/2

Engines made by

Blair & Co.

When made

1876

Length of Stroke

33

Boilers made by

Do.

When made

1876

Pressure of Steam

70 lbs.

If Surveyed Afloat or in Dry Dock

Union S. Dock

(State name of Dock.)

Classed

90A1

Registered Horse Power

99

Last Survey No.

Port

Particulars of Repairs and Examination

In Annual Survey

(State cause of Repairs.)

Vessel placed in dry dock, sea connections examined & found to be in good condition, propeller & its connections sound & tail shaft down 4" in stern bush. Boiler examined stays & furnaces found to be in good condition, middle combustion chamber common to two furnaces, a part of this has been cut out & a new rivetted patch fitted. Stues in good condition. Safety valves examined found in good condition, & set under steam to the working pressure of 70 lbs per sq. in. The High Pressure cylinder has been tried out & a new piston fitted.

General Observations, Opinion, and Recommendation:—

The Boiler being now in good & safe working condition & the machinery as far as seen renders the vessel eligible in my opinion to remain as classed & have the certification B. S. 4. 84 recorded provided that the boiler is again examined within 12 mths. as per rule

Entry or Registering Fee... £ - : - : -

Survey Fee (per Section 28) ... £ 2 : 2 : 6

Certificate (if required) ... £ 1 : 2 : 6

(Travelling Expenses, if any, £)

received by me,

17/4/84

1884

Geo. E. Wilkinson

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute

FRIDAY 13 APRIL 1884

188

Assigned

B. S. 4. 84

(State if Report is also sent on the Hull of the Ship)

(Condition of Engines and Boilers, and subsequent Repairs and Examinations, to be clearly stated.)

(The Surveyors are requested not to write on or below the space for Committee's Minute.)

[Form No. 9-3000, 29/12/82.]

Insert Character precisely as in the Register Book.



It is submitted that this vessel is
eligible to have the notification
B.S. 4.84 recorded, the boilers being
subject to Resurvey as per Rule

D.P.

8/4/84



© 2021

Lloyd's Register
Foundation

Department of Survey for Boilers of Engines and Boilers.