

43741 #37112

Report of Survey for Repairs of Engines and Boilers.

No. _____ (Received at London **TUESDAY 1 APRIL 1884**)

No. in Reg. Book. 106 Survey held at London Date, first Survey Mar. 7th Last Survey Mar. 29th 1884

on the Machinery of the S S "Ada" (Number of Visits 6)

Tonnage, Gross <u>47</u>	Built at <u>London</u>	When built <u>1875</u>
Ditto, Net <u>13</u>	Owners <u>Phillips & Francis</u>	Port belonging to <u>London</u>
Diameter of Cylinder <u>15 1/4 + 27 5/8</u>	Engines made by <u>J & W. Dudgeon</u>	When made <u>1875</u>
Length of Stroke <u>14"</u>	Boilers made by <u>Do</u>	When made <u>1875</u>
Pressure of Steam <u>60 lbs.</u>	If Surveyed Afloat or in Dry Dock <u>Summiton: D.R. & Aft.</u>	Classed <u>100A1</u>
Registered Horse Power _____	(State name of Dock.)	Character in Register Book.
Last Survey No. _____	Port <u>L.M.C. 4.82.</u>	

Particulars of Repairs and Examination In Annual Survey.

Vessel placed in dry dock sea connections examined & found to be in good condition, propeller & its connections sound & tail shaft a good fit in stern bush. Boiler lifted out, & a new plate fitted the whole length of boiler about 4 ft broad at bottom & a new front plate carried up to half diameter of furnaces about 16 new screwed stays have been renewed. furnaces & combustion chambers in good condition. Safety valves in good condition & loaded to 60 lbs per sq. in. Boiler replaced in vessel.

It is submitted that this vessel is eligible to have the notification B.S. 3.84 recorded, the boiler being subject to re-examination as per Rule.
M 29/3/84

General Observations, Opinion, and Recommendation:—

The boiler being now in good & safe working condition & the machinery as far as seen, the vessel is eligible in my opinion to remain as classed than the notification B.S. 3.84 recorded, provided that the boiler is again examined within 12 mths. as per rule.

Entry or Registering Fee... £ - : - : -
(per Section 27.) 28/4/84

Survey Fee (per Section 28) ... £ 1 : 1 : 7 received by me, 29/3/84

Certificate (if required) ... £ 2 : 6 : 11
to be sent as per margin.

(Travelling Expenses, if any, £ _____)

Geo. E. Williamson
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute TUESDAY 29 APRIL 1884 188

Assigned B.S. 3.84



LON672-0416