

Report of Survey for Repairs, &c., of Engines & Boilers.

(Received at London Office, 5. 8. 84)

No. 275 on the Machinery of the S. S. "Perim" (Number of Visits 2)
 Reg. Book. Survey held at London Date, first Survey 28 July Last Survey July 29 1884
 Tonnage, Gross 1329 Built at Glasgow When built 1877
 Ditto, Net 867 Owners W. Cousens & Co. Port belonging to London
 Diameter of Cylinder 31 1/2 Engines made by Lond. & Glas. Co. When made 1877
 Length of Stroke 33 Boilers made by Do. When made 1877
 Pressure of Steam 65 lbs. If Surveyed Afloat or in Dry Dock Union S. Dock (State name of Dock.)
 Registered Horse Power 160 Classed 100 A1
 Last Survey No. Port L.M.C. 8.81.

Particulars of Repairs and Examination For Annual Survey.

(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

Vessel placed in dry dock sea connections examined & found to be in good condition. Propeller disconnected tail shaft drawn in, examined, & found to be in good condition, the stern bush relined & a new propeller fitted. Boilers examined, test holes drilled in bottoms of combustion chambers, plates found to be but little deteriorated. Furnaces & Stays & Shells in good condition. Safety Valves examined & found to be in good condition.

General Observations, Opinion, and Recommendation:—

(State clearly what alteration, if any, is suggested to be made in the existing notification of the vessel's machinery in the Register Book, consequent upon this survey.)

in good & safe working condition & the engines as far as seen, the vessel is eligible in my opinion to remain as classed & than the notification B.S. 7.84 recorded provided that the boilers are again examined within 12 mths. as per rule.

Survey Fee (per Section 28) 28/8/84 £ 2 : 2 :
 Special Damage Fee (per Section 28) £ : :
 *Certificate (if required) £ : 5 :
 Travelling Expenses (if chargeable) £ : :

received by me,
1884


W. E. Milner
 Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute

FRIDAY 29 AUGUST 1884

Assigned

B.S. 7.84




Lloyd's Register
 Foundation

LON 673-0176

It is submitted that this vessel is
eligible to have the notification
BS. 7.84 recorded the boilers being
subject to resurvey as per Rule

Wt

2/8/84.



© 2021

Lloyd's Register
Foundation