

Report of Survey for Repairs, &c., of Engines & Boilers.

FRIDAY 5 SEPT 1884

No.

No. in Reg. Book. Survey held at *London*

Date, first Survey and Last Survey *Aug. 30th 1884*

49 on the Machinery of the *S. S. "Palmyra"*

(Number of Visits *1*)

Tonnage, Gross *960*

Built at *Newcastle*

When built *1866*

Ditto, Net *707*

Owners *Lon. Str. Shippg. Co.* Port belonging to *London*

Diameter of Cylinder *25 & 48*

Engines made by *R & W Hawthorn & Co.* When made *1866*

Length of Stroke *30*

Boilers made by When made *1872*

Pressure of Steam *75 lbs.*

If Surveyed Afloat or in Dry Dock *Aft. Lon. Docks* Classed *90A1*

Registered Horse Power *140*

Last Survey No. *6207* Port *Dpts.*

M.S. 3. 80. B.S. 5. 83

Particulars of Repairs and Examination *An Annual Boiler Survey*

(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

*Examined Main Boiler, Furnaces in good condition
Combustion chambers slightly buckled, holes drilled
in bottom found to be full. 56 some of the screwed stays
found to be corroded & two of the stays in steam space.
Shells of boilers found in good condition. Superheater
found in good condition. Safety valves in good con-
dition & loaded with lever weights to 75 per sq. in.*

General Observations, Opinion, and Recommendation:—

(State clearly what alteration, if any, is suggested to be made in the existing notification of the vessel's machinery in the Register Book, consequent upon this survey.)

*The boilers being now in
good & safe working condition renders the vessel eligible
in my opinion to remain as classed than the notification
B. S. 8. 84 recorded provided that the boilers are again
examined within 12 mths. as per rule.*

Office or Registration Fee (per Sec. 27) £ : :

Survey Fee (per Section 28) *8/9/84* £ 1 : 1

Special Damage Fee (per Section 28) £ : :

Certificate (if required) £ : :

Travelling Expenses (if chargeable) £ : :

received by me,

10/9 1884

J. L. E.

Geo. C. Merriam


Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute

Assigned

TUESDAY 9 SEPT 1884

B. S. 8, 84



Lloyd's Register
Foundation

LONG 73-0229

It is submitted that this vessel is
eligible to have the notification
B.S. & 84 recorded, the boilers being
subject to resurvey as per Rule

W.P.

4/9/84



© 2021

Lloyd's Register
Foundation