

Report of Survey for Repairs of Engines and Boilers.

No.

(Received at London Office) **TUESDAY 17 FEB 1885**

No. in Reg. Book. Survey held at London

Date, first Survey Feb. 5th Last Survey Feb. 11th 1885

470 on the Machinery of the S. S. "Trevethick"

(Number of Visits 4)

Tonnage, Gross 779

Built at Newcastle

When built 1866

Ditto, Net 489

Owners J. Funnell & Son

Port belonging to Newcastle

Diameter of Cylinder 26" x 51"

Engines made by Vic. & Co. Eng. Works Co.

When made 1873

Length of Stroke 30"

Boilers made by Do.

When made 1873

Pressure of Steam 75 lbs.

If Surveyed Afloat or in Dry Dock Pontoon
(State name of Dock.)

Classed

Years assigned.

Character in Register Book.

A 1

Registered Horse Power 99

Last Survey No.

Port

B.M.S. 1.84.

Particulars of Repairs and Examination In Annual Survey

(State cause of Repairs.)

Vessel placed on pontoon, sea connections examined found to be in good condition. Propeller disconnected Tail shaft examined found to be somewhat corroded between liners the liners sound. A new brass bush has been fitted in stern tube & the shaft & propeller replaced. Boilers examined furnaces, combustion chambers, & shells found in good condition, nine new stays fitted in backs of comb. chms. & six fore & aft stays. Superheater examined, bottom found to be slightly pitted, this has been covered with Portland cement. Stays good. Weighted lever safety valves found to be loaded to 75 lbs. per sq. in.

General Observations, Opinion, and Recommendation:— The boilers being now in good safe working condition & the machinery as far as seen, the vessel is eligible in my opinion to remain as classed & the certification B. S. 2. 85 recorded provided that the boilers are again examined within 12 mths. as per rule.

Entry or Registering Fee... £ : :

Survey Fee (per Section 28) ... £ 1 : 1

Certificate (if required) ... £ : :
to be sent as per margin.

(Travelling Expenses, if any, £)

Committee's Minute

FRIDAY 20 FEB 1885

188

Assigned

B. S. 2, 85

received by me,
13/2/85 1885

Geo. E. Merriam
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Lloyd's Register
Foundation

LOW674-0245

It is submitted that this vessel
is eligible to have the notification
B.S. 2.85 recorded the boiler
being subject to survey as
per Rule.

DP
14/2/85



© 2021

Lloyd's Register
Foundation

REGISTERED OFFICIALS OF THE LLOYD'S REGISTER FOUNDATION