

44493
Report of Survey for Repairs, &c., of Engines & Boilers.

No. _____ (Received at London Office, TUESDAY 17 MARCH 1885)
No. in Reg. Book. Survey held at London Date, first Survey Mar: 2 Last Survey Mar: 12 1885
1091 on the Machinery of the S. S. 'Compton' (Number of Visits 5)
Tonnage, Gross 1804 Built at Newcastle When built 1878-1
Ditto, Net 1186 Owners W. Milburn & Co. Port belonging to London
Diameter of Cylinder 32" & 62" Engines made by J. Shaw & Co. When made 1878
Length of Stroke 42 Boilers made by Do. When made 1878
Pressure of Steam 70 lbs. If Surveyed Afloat or in Dry Dock S. S. 'Compton' Classed 100 A 1
Registered Horse Power 200 (State name of Dock.)
Last Survey No. _____ Port L.M.C. 9.83.

Particulars of Repairs and Examination For Annual Survey
(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

Vessel placed in dry dock, sea connections examined & found to be in good condition, Propeller & its connections sound, & the tail shaft a good fit in stern bush. —
Boilers examined all found in good condition with the exception of some leaks in bottoms of shells which have been caulked, & six fitted bolts in lieu of defective rivets in seams underneath. Safety valves examined found to be in good condition & ~~test~~ ^{tested} under steam to the working pressure of 70 lbs per sq. in.

General Observations, Opinion, and Recommendation:— The boiler being now in
(State clearly what alteration, if any, is suggested to be made in the existing notification of the vessel's machinery in the Register Book, consequent upon this survey.)
good & safe working condition renders the vessel
eligible in my opinion to remain as Classed than
the notification B. S. 3.85 recorded.

Office or Registration Fee (per Sec. 27) £ : :
Survey Fee (per Section 28) 16/3 £ 7 : 7
Special Damage Fee (per Section 28) £ : :
Certificate (if required) £ : 5 :
Travelling Expenses (if chargeable) £ : :
Committee's Minute

received by me, G. E. Milburn
18 1885

G. E. Milburn
Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

FRIDAY 27 MARCH 1885
B. S. 3.83

Assigned



Lloyd's Register
Foundation
LON 674-0397

It is submitted that this vessel is
eligible to have the notation
BS 3.85 recorded the boilers being
subject to survey as per Rule

WQ
16/3/85



© 2021

Lloyd's Register
Foundation