

Report of Survey for Repairs, &c., of Engines & Boilers.

No. 44963
TUESDAY 19 MAY 1885
No. in Reg. Book. Survey held at London Date, first Survey Apl. 13 Last Survey Apl. 29 1885
399 on the Machinery of the S. S. "Glencoe" (Number of Visits 2)
Tonnage, Gross 2913 Built at Glasgow When built 1878-11
Ditto, Net 1901 Owners M. E. Lugin Gw & Co. Port belonging to Glasgow
Diameter of Cylinder 48" x 88" Engines made by Son: & Glas: Co. When made 1878
Length of Stroke 60" Boilers made by Do. When made 1878
Pressure of Steam 75 lbs. If Surveyed Afloat or in Dry Dock (State name of Dock.) Character in Register Book.
Registered Horse Power 550. Classed 100 A1
Last Survey No. Port L.M.C. 1.83.

Particulars of Repairs and Examination For Annual Survey
(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from repairs due to other causes. State also the dates and initials of any letters respecting this case.)
Examined two main boilers, double ended with through furnaces, several small blisters in furnaces which have been pared, some with rivets through, & one cut out & patched. one large blister 6 1/2 x 5 1/2 x 3/16 pared but appears sound. the remaining parts of boilers found to be in good condition. Safety valves in good condition.

General Observations, Opinion, and Recommendation:— The boilers being now in good & safe working condition renders the vessel eligible in my opinion to remain as classed & have the notification B. S. 4. 85 recorded provided that the boilers are again examined within 12 mths. as per rule.

or Registration Fee (per Sec. 27) £ : :
ey Fee (per Section 28) 23/5/85 £ 1 : 1 :
al Damage Fee (per Section 28) £ : :
tificate (if required) £ : 5 :
elling Expenses (if chargeable) £ : :
received by me 176 1885
Geo. C. Wilkinson
Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute FRIDAY 22 MAY 1885

Signed

It is submitted that this vessel
is eligible to have the notification
B.S. 485 recorded the boiler being
subject to resurvey as per rule

D.P.
18/5/85

= = =



© 2021
Lloyd's Register
Foundation