

Report of Survey for Repairs, &c., of Engines & Boilers.

45293

No. 675 (Received at London Office, FRIDAY 20 AUGUST 1885)
 No. in Reg. Book. Survey held at London Date, first Survey July 31 Last Survey 17 Aug 1885
815 on the Machinery of the S.S. "Sydian Monarch" (Number of Visits 5)
 Tonnage, Gross 3987 Built at Dumbarton. When built 1881-5
 Ditto, Net 2595 Owners Royal Exch. Shpg. Co. Port belonging to London
 Diameter of Cylinder 46 7/8 Engines made by D. Rowan When made 1881
 Length of Stroke 57 Boilers made by (i) Do. When made 1881
 Pressure of Steam 80 lbs. If Surveyed Afloat or in Dry Dock Millwall D. Dock (State name of Dock.)
 Registered Horse Power 500 Classed 100 A1
 Last Survey No. 781 Port L.M.C. 7.81

Particulars of Repairs and Examination For S.S. No. 1.
 (State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

Vessel placed in dry dock, sea connections examined & found in good condition, propeller & its connections sound, Stern bush worn down 7/8". H. P. piston examined & found to be in good condition, Examined crank shaft, thrust & tunnel shafting, all found in good condition, air, circulating, feed & bilge pumps & valves & pumping arrangements all found to be in good condition.
 The lignum vitae in stern tube has been renewed, examined the H.P. & L.P. slides & low pressure cylinder & found them in a good condition
 Examined the three main boilers with 4 corrugated furnaces & 1 dome & found them in a good condition
 105 boiler tubes have been renewed.


General Observations, Opinion, and Recommendation: As far as seen the machinery of this vessel is in a safe working condition and eligible in my opinion to have the notification + L.M.C. 7.85 recorded in the Register Book provided the safety valves are found to blow at 80 lbs pressure on the vessels return from her present voyage. (one month).

Office or Registration Fee (per Sec. 27) £ : :
 Survey Fee (per Section 28) £ 4 4 -
 Special Damage Fee (per Section 28) £ : :
 *Certificate (if required) £ : 5 -
 Travelling Expenses (if chargeable) £ : :

received by me, 23/9 1885
C. H. Brown & Geo. C. Wilkinson
 Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute
Assigned

TUESDAY 1 SEPT 1885



LON 675-0415

Insert Character of Ship and Machinery precisely as in the Register Book.

It is submitted that this vessel is eligible to have the notification Lm 6 8.85 recorded subject to the safety valves being tested on the vessels return

W.F.
27/8/85.

