

Report of Survey for Repairs, &c., of Engines & Boilers.

(Received at London Office,

TUESDAY 15 SEPT 1885

45362

No. 303 on the Machinery of the S. S. "Persian Monarch" (Number of Visits 5)
 No. in Reg. Book. 303 Survey held at London Date, first Survey 19. Aug Last Survey 1 Sept 1885
 Tonnage, Gross 3923 Built at Dumbarton When built 1880 9
 Ditto, Net 2569 Owners Royal Exchange S. Co. Port belonging to London
 Diameter of Cylinder 46 87 Engines made by D. Rowan When made 1880
 Length of Stroke 57 Boilers made by (i) 1880
 Pressure of Steam 80 If Surveyed Afloat or in Dry Dock Millwall Dock Classed 100 A 1
 Registered Horse Power 185 Character in Register Book.
 Last Survey No. 11. 80 Port + L.M.C.

Particulars of Repairs and Examination

Special Survey No 1.

(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

Examined Seacocks & connections and found them in a good condition.

New lignum vitae has been fitted in the stern tube. Examined the 3 main (double ended) and 2 donkey boilers, ^{+ donkey} found them in a good condition. 9 of the ¹² corrugated furnaces are said to be of steel. The seams between these furnaces & the tube plates have been riveted.

Examined the safety valves, high & low pressure slides and cylinders and the pumps and found them in a good condition.

Examined the crank wrist tunnel & tail shafts & found them good.

The safety valves were set to blow at 80 lb pressure.

General Observations, Opinion, and Recommendation:—

(State clearly what alteration, if any, is suggested to be made in the existing notification of the vessel's machinery in the Register Book, consequent upon this survey.)

The machinery of this vessel appears to be in a safe working condition and is in my opinion eligible to have the notification + L.M.C. 9.85 recorded in the Register Book.

Office or Registration Fee (per Sec. 27)	£	:	:	} received by me, <u>J.H.H.</u> <u>14/10 1885</u>
Survey Fee (per Section 28) <u>45/9/85</u>	£	4	4	
Special Damage Fee (per Section 28)	£	:	:	
*Certificate (if required)	£	:	5	
Travelling Expenses (if chargeable)	£	:	:	


J.H.H.
Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute

FRIDAY 26 SEPT 1885

Assigned

+ L.M.C. 9.85



Lloyd's Register Foundation

LONG15-0502

The Surveyors are requested not to write on the space for Committee's Minute.

Insert Character of Ship and Machinery precisely as in the Register Book.

It is submitted that this vessel
is eligible to have the notification
Lmb. 9.55 recorded.

D J
14/9/55.

