

Report of Survey for Repairs, &c., of Engines & Boilers.

45427

No. _____ (Received at London Office, _____)

No. in Reg. Book. Survey held at London Date, first Survey Sep. 29 Last Survey Oct 7 1885

65 on the Machinery of the S. S. "Sanfield" (Number of Visits 3)

Tonnage, Gross 765 Built at Newcastle When built 1864-12

Ditto, Net 482 Owners A. James Port belonging to London

Diameter of Cylinder 25 1/4 Engines comp. made by R. & W. Hawthorn When comp. made 1877

Length of Stroke 30 Boilers made by Do. When made 1877

Pressure of Steam 75 lbs. If Surveyed Afloat or in Dry Dock Pontoon & Aft. Classed A 1

Registered Horse Power 90 (State name of Dock.)

Last Survey No. _____ Port _____ L.M.C. 6.83 B.S. 4.84

Particulars of Repairs and Examination In Annual Survey

(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

Vessel placed on Pontoon, sea connections examined and found to be in good condition, propeller & its connections sound & the stern bush worn down 8".

Boilers examined, furnaces, combustion chambers & screwed stays found to be in good condition, a few rivets renewed in patch in port wing furnace. Four stays in Steam space of Port boiler found to be slightly corroded but not sufficiently to be renewed. Safety valves in good condition & tested under steam to 75 lb.

General Observations, Opinion, and Recommendation:—

(State clearly what alteration, if any, is suggested to be made in the existing notification of the vessel's machinery in the Register Book, consequent upon this survey.)

The boilers being now in good & safe working condition the machinery as far as seen, the vessel is eligible in my opinion to remain as classed than the notification B.S. 10.85 recorded provided that the boilers are again examined within 12 mths. as per rule.

Office or Registration Fee (per Sec. 27)	£	:	:	received by me, <u>YBN</u> <u>20/10 1885</u>
Survey Fee (per Section 28) <u>19/10/85</u>	£	1	1	
Special Damage Fee (per Section 28)	£	:	:	
*Certificate (if required)	£	:	:	
Travelling Expenses (if chargeable)	£	:	:	

Committee's Minute _____

Assigned _____

FRIDAY 16 OCT 1885

B.S. 10 85

Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

It is submitted that this vessel
is eligible to have the notification
B.S. 10.55 recorded the boilers
being subject to resurvey
as per Rule.

D F

8/10/85



© 2021

Lloyd's Register
Foundation