

Report of Survey for Repairs, &c., of Engines & Boilers.

45466

(Received at London Office,

FRIDAY 2^o AUGUST 1885)

No. 516 on the Machinery of the S.S. "Dunrobin Castle" (Number of Visits 2)
 Survey held at London Date, first Survey Apr. 24 Last Survey 18 Aug 1885
 Tonnage, Gross 2812 Built at Glasgow When built 1875-11
 Ditto, Net 1797 Owners D. Currie & Co Port belonging to London
 Diameter of Cylinder 47 & 75 Engines made by R. Napier & Sons When made 1875
 Length of Stroke 48 Boilers made by Do. When made 1875
 Pressure of Steam 60 lbs. If Surveyed Afloat or in Dry Dock Afloat & Greig's D. Dock. Classed 100 A1
 Registered Horse Power 300 (State name of Dock.) SS do 2 83 6.85
 Last Survey No. 45733 Port Lon L.M.C. 12.83

Particulars of Repairs and Examination For Annual Survey

(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)


Vessel placed in dry dock sea connections examined & found to be in good condition, propeller & its connections sound & the tail shaft a good fit in stern bush. -
 Main boilers examined, furnaces, stays, comb. chrs. all found in good condition, ends in steam space found to be doubled. Superheater in good condition.
 The boiler tubes have been renewed & the boiler tested to 90 lbs hydraulic pressure
 The safety valves were found to blow at 60 lbs.

General Observations, Opinion, and Recommendation: - As far as seen the machinery of this vessel appears to be in a safe working condition & is in ^{our} opinion eligible to have the notification B.S. 8.85 recorded in the Register Book

Office or Registration Fee (per Sec. 27) £ : :
 Survey Fee (per Section 28) 16/11/85 £ 2 2 -
 Special Damage Fee (per Section 28) .. £ : :
 *Certificate (if required) £ : :
 Travelling Expenses (if chargeable) £ : :

received by me. Geo. E. McInnes 12.12.1885
 Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute FRIDAY 30 OCT 1885
 Assigned D.S. 8. 85



LONG 615-0627

State if a Report is also sent on the Hull of the Ship

Insert Character of Ship and Machinery precisely as in the Register Book.

It is submitted that this vessel is eligible to have the notification B.S. 8.85 recorded. The boilers being subject to resurvey as per Rule.

D.S.
27/8/85



THE LLOYD'S REGISTER OF SHIPBUILDERS & BOILERS