

45820

REPORT of SURVEY for REPAIRS, &c.

Received in London Office

4 Feb 1886

No. 1247
No. in Reg. Book. 1247
Survey held at London
Date, First Survey 5th Jan. Last Survey 27th Jan. 1886
(No. of Visits) 1
on the Iron Screw Steamer "AURORA"
Master Apostino Villa

TONNAGE:—
NET 446
GROSS 711
UNDER DEK 646
Built at Newcastle
By whom Palmers Co.
When 1863 6
Owners Enrico Zenoglio
Port belonging to London
Owner's Address Genoa
(if not already recorded in Appendix to Register Book.)

f Surveyed Afloat or in Dry Dock dry dock Name of Dock Victoria Pontons Destined Voyage Genoa.
Length of Poop ft.: of Forecastle ft.: of Raised Or. Deck ft.: Moulded Depth ft. ins.
(if these particulars are not yet recorded in the Register Book.)
Years assigned, if a Wood Ship.
Character in Register Book.

Last Survey, No. 1283 / Port London
(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Society's Freeboard (if assigned) as painted on Ship
Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and Initials of any letters respecting this case.

REPAIRS, OR EXAMINATION AS PER RULE

Part I. S. No. 3

This Vessel has been examined in the Victoria Pontons, and afloat in the Victoria Docks.

The bottom appeared to be in good order and has been cleaned and painted, but no arrangements could be made for drilling as the ownership was being transferred at the time.

The decks have since been examined with the consent of the new owner, and the undersigned recommends that the main deck should be entirely renewed excepting the portions under the two steam cranes, which parts are in good order. The fore-castle deck entirely renewed, and the poop deck renewed where worn near the gangways.

The masts, yards &c. have been examined, and it is recommended that the dead-eye bolts of the foremast and main mast should be examined and renewed where required. The lower ends of the main rigging examined, a hoop fitted to the heel of the foremast 18 ins. above P.T.O.

PRESENT CONDITION OF THE		Boats	
Decks	see remarks	3	good
Waterways	good	Masts, Yards, &c.	see remarks
Comings	in fair order	Condition, how ascertained	examined
Up'r Dk. Beams & Fastenings	good	Sails	not examined
Low'r Dk. Beams & Fastenings	"	Anchors	No. of 3 B. 1 S. 2 K
Planksheers	"	Cables	Part seen good
Sheerstrakes	"	Hawsers & Warps	not examined
Topsides	"	Standing & Running Rigging	see remarks
Wales	"		
Engine Room Skylights	good	Coal Bunker, Openings, Lids, &c.	good
General Observations, Opinion as to Class, &c.:		Scuppers	good
		Cargo & Main Hatchways	fairly good
		Hatches	need repair

This Vessel so far as seen is in the condition described herein and in my opinion is entitled to retain her class until her arrival in Genoa when the survey should be completed.

Entry Fee (if chargeable) per Scale I., Sec. 27. £ : :
Office Fee (if chargeable) per Scale II., Sec. 27. £ : :
Survey Fee (per Section 28) £ : :
Special Damage Fee (if any) (per Sec. 28) £ : :
Certificate (if required) to be sent as per margin £ : :
Travelling Expenses (if chargeable) £ : :
Second Surveyor's Fee (if any) £ : :
received by me, 188

Committee's Minute

Character assigned

FRIDAY 5 FEB 1886

Surveyor to Lloyd's Register of British & Foreign Shipping.

3-2-86

Lloyd's Register Foundation

the ship, the hoops on the heel of the main mast hardened up, and the masts cleaned up at the cleets, the jaff and derricks gear examined, and the stow examined and renewed if required.

The survey has not been proceeded with beyond ^{this and} an inspection of the holds which were found in fair order, as the new owners are very desirous of having it completed at Genoa for which Port the vessel is chartered, and they have written a letter requesting to be allowed to do so, which is herewith attached, and which refers in like manner to the survey of the steamer "Italia".

The undersigned begs to submit the case for the favourable consideration of the Committee.

Chas H. Jordan
2-2-86.



© 2021

Lloyd's Register
Foundation