

# Report of Survey for Repairs, &c., of Engines & Boilers.

(Received at London Office.)

TUESDAY 9 FEB 1886

No. 125 in Survey held at London Date, first Survey 12 Jan Last Survey 5 Feb 1886  
 Reg. Book. 125 on the Machinery of the S.S. Vestrel (Number of Visits 3)  
 Tonnage, Gross 960 Built at Dundee When built 1878  
 Ditto, Net 586 Owners General Steam Nav. Co Port belonging to London  
 Diameter of Cylinder 34 + 56 Engines made by Howley Bros. When made 1878  
 Length of Stroke 36 Boilers made by Do. When made 1878  
 Pressure of Steam 65 If Surveyed Afloat or in Dry Dock Deptford Dock (State Name of Dock.)  
 Registered Horse Power 155 Classed 100 A 1  
 Last Survey No. 2.85 Port London Lm b 6.81.

## Particulars of Repairs and Examination

(State clearly the cause of Repairs if any, and in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

of machinery in accordance with the requirements of the Rules for S.S. No. 2.

Examined cylinders, slides, all pumps, crank shaft & sea connections & found them in good condition.

Donkey boiler examined & found good.

Main boilers examined & found in fair condition except furnaces which were badly cracked round the flanged strengthening rings.

The old furnaces have been cut out & replaced by plain new ones and tested by water pressure to 100 per square inch satisfactorily.

## General Observations, Opinion, and Recommendation:—

(State clearly what alteration, if any, is suggested to be made in the existing notification of the vessel's machinery in the Register Book, consequent upon this survey.)

is now in good order and safe working condition and eligible in my opinion to have the notification Lm b 2.86 recorded Subject to the resurvey of boilers as per Rule.

Office or Registration Fee (per Sec. 27) £ : :  
 Survey Fee (per Section 28) £ 3 : 0  
 Special Damage Fee (per Section 28) £ : :  
 \*Certificate (if required) £ : :  
 Travelling Expenses (if chargeable) £ : :

received by me,  
 15.2.1886

David Purves.

Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

FRIDAY 12 FEB 1886

Committee's Minute

Assigned



© 2021

Lloyd's Register  
 Foundation  
 LON 676-0472