

Report of Survey for Repairs, &c., of Engines & Boilers.

No. 10.

(Received at London Office, TUESDAY 16 FEB 1886)

Reg. I No. in Survey held at *London* Date, first Survey *Dec 8/85* Last Survey *Feb 12 1886*

688 on the Machinery of the *S. S. "Erl King"* (Number of Visits *5*)

Tonnage, Gross *2193* Built at *Glasgow* When built *1865-9*

Ditto, Net *1418* Owners *W. Ross & Co.* Port belonging to *Glasgow*

Diameter of Cylinder *36" x 70"* Engines made by *D. Rollo & Sons* When made *1881*

Length of Stroke *48"* Boilers made by *Do.* When made *1881*

Pressure of Steam *85 lbs.* If Surveyed Afloat or in Dry Dock *Ant. & aft.* Classed *100 A1*

Registered Horse Power *250* (State name of Dock.)

Last Survey No. *Port* *T.L.M.C. 9. 81.*

Particulars of Repairs and Examination *For Special Survey No. 1.*
(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from repairs due to other causes. State also the dates and initials of any letters respecting this case.)

Vessel placed on Pontoon, sea connections examined & found to be in good condition, Propeller & its connections sound & the tail shaft down 1/4" in Stern bush.

Examined pistons, cylinders, slides, air circulating, feed & bilge pumps, valves, & pumping arrangements: all found to be in good condition. Crank shaft, Thrust & tunnel shaft " " Main trilers examined internally & externally & found to be in good condition.

Safety valves in good condition & found to lift at 85 lbs & under steam.

It is submitted that this vessel is eligible to have T.L.M.C. 2. 86 recorded the boilers being subject to Renewal as per Rule

General Observations, Opinion, and Recommendation:— *The machinery being now in good & safe working condition renders the vessel eligible in my opinion to be marked in the Register Book with T.L.M.C. 2. 86.*

Office or Registration Fee (per Sec. 27) £ : :
Survey Fee (per Section 28) £ *3 : 3*
Special Damage Fee (per Section 28) £ *31/5/87*
*Certificate (if required) £ : :
Travelling Expenses (if chargeable) £ : :
received by me *25.6.1887*

Geo. E. Wilkinson.
Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute
Assigned *+ DMB 2. 86*

TUESDAY 2 MARCH 1886



LON676-0545