

45978

Report of Survey for Repairs, &c., of Engines & Boilers.

(Received at London Office, FRIDAY 19 MARCH 1886)

No. 660 in Survey held at London Date, first Survey Feb. 11 Last Survey Feb. 11 1886
Reg. Book. on the Machinery of the S.S. "Lord of the Isles." (Number of Visits 1 Year Month)
Tonnage, Gross 2484 Built at Glasgow When built 1870-6
Ditto, Net 1536 Owners Shaw Bushby & Co. Port belonging to London
Diameter of Cylinder 44" x 76" Engines made by C. D. Holmes & Co. When made 1878
Length of Stroke 48" Boilers made by Do. When made 1878
Pressure of Steam 75 lbs. If Surveyed Afloat or in Dry Dock Pender's D. Dock Character in Register Book.
Registered Horse Power 350 (State Name of Dock.) Classed 100A1
Last Survey No. Port L.M.C. G. 32.

Particulars of Repairs and Examination In Annual Survey.

(State clearly the cause of Repairs if any, and in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

Vessel placed in dry dock, sea connections examined found to be in good condition. Propeller disconnected, a slight crack found in featherway at after end of boss, a hole has been bored at end of crack, tail shaft examined, found in good condition, the stem bush renewed & the whole refitted.

General Observations, Opinion, and Recommendation :-- The machinery as far as seen

(State clearly what alteration, if any, is suggested to be made in the existing notification of the vessel's machinery in the Register Book, consequent upon this survey.)

appears in good condition rendering the vessel eligible in my opinion to remain as classed.

Office or Registration Fee (per Sec. 27) £ : :
Survey Fee (per Section 28) £ : :
Special Damage Fee (per Section 28) £ : :
*Certificate (if required) £ : :
Travelling Expenses (if chargeable) £ : :


received by me,
188

Geo. E. Milnerman
Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute

Assigned

TUESDAY 23 MARCH 1886



Lloyd's Register
Foundation

LON677-0077

It is submitted that this vessel
is eligible to remain as classed

D.P.
18/3/86



© 2021

Lloyd's Register
Foundation