

REPORT of SURVEY for REPAIRS, &c.

No. 46233

Received in London Office.

Tuesday, 1st June, 1886.

No. in Reg. Book. Survey held at London

Date, First Survey 18th May Last Survey 19th May 1886

462 on the Steel Screw Steamer AUSTRAL

Master A. Charlton

TONNAGE:—

NET 3271

Built at Glasgow

By whom J. Elder & Co.

When 1881

GROSS 5589

Owner's Orient Steam Navigation Co.

Port belonging to Glasgow

UNDER DK. 5315

Owners' Address (if not already recorded in Appendix to Register Book.)

If Surveyed Afloat or in Dry Dock dry dock Name of Dock Royal Albert Destined Voyage Australia

Length of Poop ft.: of Forecastle ft.: of Raised Qr. Deck ft.: Moulded Depth ft. ins. (if these particulars are not yet recorded in the Register Book.)

Classed

Years assigned, if a Wood Ship.

Character in Register Book.

Last Survey, No. 45774 Port London

58103-84

100 A1  
1,86

(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and Initials of any letters respecting this case.)

REPAIRS, OR EXAMINATION AS PER RULE

Condition.

This Vessel has been examined in the Royal Albert dry dock and afloat in the Royal Albert dock.

The bottom found in good order has been cleaned & painted. A few rivets have been renewed in the rudder plating.

The chain cables have been roused in the dock, and 300 fms found complete and in good order.

The after promenade deck has been extended forward for a distance of 18 feet, and out to the sides of the vessel, the new beams being of the same size as the original, and a stringer has been added to the ends of the beams 15 x 3/16 for the whole length of the structure.

The couplings of the two engine room skylights have been raised 3' 6" above those originally fitted.

PRESENT CONDITION OF THE

|                              |      |                                  |      |                                      |      |                            |            |      |
|------------------------------|------|----------------------------------|------|--------------------------------------|------|----------------------------|------------|------|
| Decks                        | Good | Plank (Bottom) & Counter         | Good | Ceiling                              | Good | Boats                      | 10         | Good |
| Waterways                    |      | Treenails or Rivets              |      | Rudder                               | "    | Masts, Yards, &c.          |            | "    |
| Comings                      |      | Breasthooks & Stemson            |      | Windlass & Capstan                   | "    | Condition, how ascertained | from data  |      |
| Up'r Dk. Beams & Fastenings  |      | Transoms, Pointers, & Crutches   |      | Pumps                                | "    | Sails                      |            | Good |
| Low'r Dk. Beams & Fastenings |      | Timbers of Frame at the openings |      | Cement (if Iron Ship)                |      | Anchor No. of              | 4 B. P. 3K |      |
| Plank sheers                 |      | Ditto ditto at other places      |      | Caulking of Bottom, D'k, & Wat'rways | "    | Cables                     | Roused     | Good |
| Sheerstrakes                 |      | Keelsons                         |      | Copper, or Y.M. (State if on Felt.)  |      | Hawsers & Warps            |            | "    |
| Topsides                     |      | Clamps & Shelves                 |      | When put on                          |      | Standing & Running Rigging |            | "    |
| Wales                        |      |                                  |      |                                      |      | Hatches                    |            | "    |
| Engine Room Skylights        | Good | Coal Bunker, Openings, Lids, &c. | Good | Scuppers                             | Good | Cargo & Main Hatchways     | Good       |      |

General Observations, Opinion as to Class, &c.:

This Vessel is in a sound and efficient condition and eligible in my opinion to remain as classed.

|   |   |   |   |                     |
|---|---|---|---|---------------------|
| Entry Fee (if chargeable) per Scale I., Sec. 27.    | £ | : | : | received by me, 188 |
| Office Fee (if chargeable) per Scale II., Sec. 27.  | £ | : | : |                     |
| Survey Fee (per Section 28)                         | £ | : | : |                     |
| Special Damage Fee (if any) (per Sec. 28)           | £ | : | : |                     |
| *Certificate (if required) to be sent as per margin | £ | : | : |                     |
| Travelling Expenses (if chargeable)                 | £ | : | : |                     |
| Second Surveyor's Fee (if any)                      | £ | : | : |                     |

Committee's Minute

Character assigned

Tuesday, 8th June, 1886.

Chas. E. Jordan  
Surveyor to Lloyd's Register of British & Foreign Shipping.