

Report of Survey for Repairs, &c., of Engines & Boilers.

(Received at London Office, 1886)

TUESDAY 18 MAY 1886

No. *46273*
 No. in Reg. Book. *278* Survey held at *London* Date, first Survey *26 March* Last Survey *5 May 1886*
 on the Machinery of the *S. S. Osprey* (Number of Visits) Year Month
 Tonnage, Gross *1095* Built at *Stockton* When built *1877 9*
 Ditto, Net *557* Owners *General Steam N.C.* Port belonging to *London*
 Diameter of Cylinder *43 80* Engines made by *Blair & Co* When made *1877*
 Length of Stroke *45* Boilers made by *(C)* When made *1877*
 Pressure of Steam *75* If Surveyed Afloat or in Dry Dock *General S. H. Co. Glasgow* Character in Register Book. *100 A1*
 Registered Horse Power *250* (State name of Dock.)
 Last Survey No. *LMC 881* Port *BS 6.85.*

Particulars of Repairs and Examination

Special Survey

(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

Examined Leacocks & connections & found New good.

The tailshaft was drawn in and found good, newignum rital and a new propeller key have been fitted.

Examined the crankshaft & found it good.

Examined the 3 main and the donkey boilers & found them good. The main boilers have been retubed.

Examined the safety valves, high and low pressure slide valves and cylinders and the pumps and found New good.

The safety valves were found to blow off at 75 lbs.

General Observations, Opinion, and Recommendation:— *The machinery of this vessel is in a safe working condition and eligible in our opinion to have the notification L. M. C. 5. 86 recorded in the Register Book*

Office or Registration Fee (per Sec. 27) £ *2 12 6*
 Survey Fee (per Section 28) £ *4 4 -*
 Special Damage Fee (per Section 28) £ *1 7 1886*
 *Certificate (if required) £ *1 7 1886*
 Travelling Expenses (if chargeable) £ *1 7 1886*

J. C. L. Spence
 Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

TUESDAY 22 JUNE 1886

Committee's Minute

Assigned

