

REPORT of SURVEY for REPAIRS, &c.

46511

No. 46511

Received in London Office,

FRIDAY 3 SEPT 1886

No. in Reg. Book. 596 Survey held at London Date, First Survey 21 August Last Survey 21 August 1886
 on the Iron Screw Steamer "Borghese" (late Galatea) Master
 TONNAGE:— NET 1331 GROSS 2044 UNDER DK. 1950
 Built at Sunderland By whom W. Pile & Co. When 1870 11th
 Owners Ræburn & Verel. Port belonging to Glasgow
 Owner's Address (if not already recorded in Appendix to Register Book.)

If Surveyed Afloat or in Dry Dock & Dry Dock Name of Dock Deptford Green Destined Voyage Antwerp thence to River Plate
 Length of Poop ft.: of Forecastle ft.: of Raised Or. Deck ft.: Moulded Depth ft. ins.
 (if these particulars are not yet recorded in the Register Book.)

Classed 100 A.1
 Last Survey, No. 4112 Port Glasgow S.L. Cl. No. 3-77. S.L. Cl. No. 1-82. 9.85
 (State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Society's Freeboard (if assigned) in salt water ft. ins.
 Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and Initials as painted on Ship in fresh water ft. ins.
 of any letters respecting this case.

REPAIRS, OR EXAMINATION AS PER RULE

This vessel has been placed in dry dock; the bottom outside examined as a part of the special survey No. 2. The lower pintle of the rudder renewed. A few rivets in the rudder & in the pintles & braces renewed.

Wrote to the Owners (copy of letter attached) stating that as the special survey No. 3 was held on this vessel in 1877- the special survey No. 2 is overdue - and desired to know when the vessel will be ready to have the special survey No. 2 held. Also stated that one hatchway beam in the after hold is fractured and repaired by a doubling plate worked on the side of the same. There are five rivets in one side of the doubling plate and only three in the other side. One or two of these rivets require making good as they are not sound. Recommended that two more rivets be added on the side of the plate where at present there are only three rivets.

In the letter (attached hereto) received from the Superintendent in answer to my letter, the Sup^{dt} states that he will get all done that he can, to complete the survey next voyage.

| PRESENT CONDITION OF THE | | | | | | | |
|------------------------------|-------------|--|------|---|------|----------------------------|----------------|
| Decks | good | Plank (Bottom) & Counter | good | Ceiling | good | Boats | good |
| Waterways | 5- | Treenails or Rivets | 5- | Rudder | 5- | Masts, Yards, &c. | 5- |
| Comings | 5- | Breasthooks and Stemson | 5- | Windlass ^{Steam winches} & Capstan | 5- | Condition, how ascertained | from deck |
| Up'r Dk. Beams & Fastenings | 5- | Transoms, Pointers , & Crutches | 5- | Pumps | 5- | Sails | good |
| Low'r Dk. Beams & Fastenings | See remarks | Timbers of Frame (at the openings) | 5- | Cement (if Iron Ship) | 5- | Anchors No. of | 3 B. 1 P. 2 K. |
| Planksheers | good | Ditto ditto at other places | 5- | Caulking of Bot'm, D'k, & Watrways | 5- | Cables | good |
| Sheerstrakes | 5- | Keelsons | 5- | Copper, or V.M. (State if on Pett.) When put on | 5- | Hawsers & Warps | 5- |
| Topsides | 5- | Champs & Shells | 5- | Scuppers | good | Standing & Running Rigging | 5- |
| Wales | 5- | | | Cargo & Main Hatchways | good | Hatches | 5- |
| Engine Room Skylights | 5- | Coal Bunker, Openings, Lids, &c. | 5- | | | | |

General Observations, Opinion as to Class, &c.:

As above stated, one beam requires slight attention. In other respects this vessel appears to be in good and efficient condition and eligible to remain as classed. The special survey No. 2 however requires to be completed.

| | | | | |
|---|---|---|---|---------------------|
| Entry Fee (if chargeable) per Scale I., Sec. 27. | £ | : | : | received by me, 188 |
| Office Fee (if chargeable) per Scale II., Sec. 27. | £ | : | : | |
| Survey Fee (per Section 28) | £ | 0 | 0 | |
| Special Damage Fee (if any) (per Sec. 28) | £ | : | : | |
| *Certificate (if required) to be sent as per margin | £ | : | : | |
| Travelling Expenses (if chargeable) | £ | : | : | |
| Second Surveyor's Fee (if any) | £ | : | : | |

Committee's Minute
 Character assigned

FRIDAY 3 SEPT 1886

J. H. Truscott
 Surveyor to Lloyd's Register of British & Foreign Shipping.