

Report of Survey for Repairs, &c., of Engines & Boilers.

(Received at London Office,

No. *46568* Port of *London*
 No. in Survey held at *London* Date, first Survey *Sept. 1* Last Survey *Sept. 25 1886*
 Reg. Book. *164* on the Machinery of the *S. S. "Mallard"* (Number of Visits *4* Year Month)
 Tonnage, Gross *1296* Built at *Dundee* When built *1882-5*
 Ditto, Net *835* Owners *Gen. S. N. Co.* Port belonging to *London*
 Diameter of Cylinder *30 1/4* Engines made by *Goulay Bros.* When made *1882*
 Length of Stroke *36* Boilers made by *Do.* When made *1882*
 Pressure of Steam *75 lbs.* If Surveyed Afloat or in Dry Dock *Afloat Brit. Dock* (State Name of Dock.)
 Registered Horse Power *140* Classified *100 A 1*
 Last Survey No. *Port* *L.M.C. 5.82*

Particulars of Repairs and Examination *For Special Survey No. 1*
 (State clearly the cause of Repairs if any, and in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

Examined by cylinders, slides, air, circulating, feed + bilge pumps + valves + found them in good condition.
Crank, thrust + tunnel shafting found in good condition
Main boilers examined internally + externally + found in good condition, Safety valves in good condition.
Donkey boiler + safety valves " " "
Vessels placed in dry dock, sea connections examined + found in good condition, propeller disconnected, tail shaft examined found to be laminated at side of Keyway, a new tail shaft has been fitted the stern bush removed + propeller refitted.
Safety valves set under steam to the working pressure of 75 lbs. □

General Observations, Opinion, and Recommendation :— *The machinery being now in good + safe working condition renders the vessel eligible in my opinion to be marked in the Register Book with*
L.M.C. 9.86

Office or Registration Fee (per Sec. 27) £ : :
 Survey Fee (per Section 28) *4/10/86* £ 3 : 3
 Special Damage Fee (per Section 28) £ : :
 *Certificate (if required) £ : :
 Travelling Expenses (if chargeable) £ : :

received by me,
19.10.1886

Geo. F. Merriam
 Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute *TUESDAY 28 SEPT 1886*

Assigned *THW + LMB G. R.*



© 2021

Lloyd's Register Foundation


2020-869007

State of a Report is also sent on the Hull of the Ship

Insert Character of Ship and Machinery precisely as in the Register Book.

It is submitted that this vessel is
eligible to have the notification Lmb
9.86 recorded.

D.P.
27/9/86



© 2021

Lloyd's Register
Foundation