

REPORT of SURVEY for REPAIRS, &c.

No. 46729 Survey held at London Date, First Survey Sept 8th Last Survey 10th Nov 1886

393 on the S Winefred Built at Chester By whom J. Bram Master E. J. Ellis

TONNAGE: NET 1359 GROSS 1359 UNDER DECK 1188 Owners Taylor and Co Port belonging to London

If Surveyed Afloat or in Dry Dock Name of Dock N. J. Dry Dock Destined Voyage Melbourne

Length of Poop ft.: of Forecastle ft.: of Raised Or. Deck ft.: Moulded Depth ft. ins. Classed

Last Survey, No. 5691 Port Hull (State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Society's Freeboard Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and Initials of any letters respecting this case.)

REPAIRS, OR EXAMINATION AS PER RULE Special Survey No. 2. At the present time place in Dry Dock

The bottom cleaned, coated and examined. The timbers and ceiling equal to 3 and more strakes lifted and examined, and found good, the cement adhering firmly to the Iron, and where worn has been thickened & mended.

The Main Keelson repaired in Midships. The Chain Bunk requiring repairs the Chain cables had to be hauled on deck and were examined, 300 fathoms in all. The Windlass was examined the last Special Survey in 1881.

The Main and Fore Masts strengthened with doubling plates at the heads & at the Main Deck Beams & hold cliffts.

Table with 4 columns: Decks, Plank (Bottom) & Counter, Ceiling, Boats. Rows include Waterways, Comings, Up'r Dk. Beams & Fastenings, Low'r Dk. Beams & Fastenings, Plank sheers, Sheerstrakes, Topsides, Wales, Engine Room Skylights, Coal Bunker, Openings, Lids, &c., Scuppers, Cargo & Main Hatchways, Hatches.

General Observations, Opinion as to Class, &c.: She is now in an efficient state and eligible to remain as classed, and to have SS London No. 2-1886, in the Register Book.

Surveyor to Lloyd's Register of British & Foreign Shipping. Senhouse Martindale

Entry Fee (if chargeable) per Scale I., Sec. 27. £ Office Fee (if chargeable) per Scale II., Sec. 27. £ Survey Fee (per Section 28) £ 5 : 5 : Special Damage Fee (if any) (per Sec. 28) £ - : - : Certificate (if required) to be sent as per margin £ - : - : Travelling Expenses (if chargeable) £ Second Surveyor's Fee (if any) £