

Report of Survey for Repairs, &c., of Engines & Boilers.

(Received at London Office, NOV 15 1886)

No. 46779 Port of London
No. in Reg. Book. Survey held at 950 on the Machinery of the S.S. "Blymene"
Date, first Survey 6 Nov^r. Last Survey 9th Nov^r 1886
(Number of Visits 2)
Tonnage, Gross 1509 Built at Stockton When built 1879
Ditto, Net 974 Owners H. J. Blake Port belonging to London
Diameter of Cylinder 32 & 60 Engines made by Blair & Co. Ltd., Stockton When made 1879
Length of Stroke 39 Boilers made by Do. When made
Pressure of Steam 82 If Surveyed Afloat or in Dry Dock Afloat
(State name of Dock.) St. Katharine's D.R. Classed 100 A 1
Registered Horse Power 140 Character in Register Book.
Last Survey No. 1052 Port Cardiff Loyds M.C. 2.83
B.S. 11.85

Particulars of Repairs and Examination

(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

Annual Survey of boilers.

Examined the main boiler and found the starboard furnace crown slightly down through being overheated, this part of the flue was heated & hammered back to its proper form.

2 New patches fitted at angles of furnace & combustion chambers. The boiler was otherwise found in good condition.

New crown stamp fitted in donkey boiler, angle iron at bottom of fire box opposite fire door corroded & leaky. Safety valves examined & found satisfactory.

General Observations, Opinion, and Recommendation:—

(State clearly what alteration, if any, is suggested to be made in the existing notification of the vessel's machinery in the Register Book, consequent upon this survey.)

This vessel is now in good order and safe working condition and eligible in my opinion to have the notification B.S. 11.86 recorded subject to the resurvey of donkey boiler in three months and the Main boilers as per Rule.

Office or Registration Fee (per Sec. 27) £ : :
Survey Fee (per Section 28) £ 1 : 1 : 0
Special on Damage, Fee (per Section 28) £ : :
*Certificate (if required) to be sent as per margin.. £ : 2 : 6
Travelling Expenses (if chargeable) £ : :
received by me, 2.12.1886

Committee's Minute

NOV 30 1886

Assigned

B.S. 11.86

Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.



Lloyd's Register
Foundation