

47287

Report of Survey for Repairs, &c., of Engines & Boilers.

No. 47287 (Received at London Office.)
 Port of London
 No. in Reg. Book. 33 Survey held at London Date, first Survey July 25th Last Survey March 2 1887
 on the Machinery of the S. S. Aberdeen (Number of Visits 3)

Tonnage, Gross 1579 Built at Aberdeen When built 1888-2
 Ditto, Net 971 Owners Adam & Co Port belonging to Aberdeen
 Diameter of Cylinder 30 + 59 Engines made by Hall Russell & Co When made 1883
 Length of Stroke 36 Boilers made by - When made 1883
 Pressure of Steam 100 If Surveyed Afloat or in Dry Dock Brown's Dry Dock Classed 100 A 1
 Registered Horse Power 156 (State name of Dock.) Character in Register Book. L.M.C. 3-83
 Last Survey No. 47099 Port Lon.

Particulars of Repairs and Examination Special Survey Number one and Damage
 (State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

Main boiler examined inside & out found in good order safety valves overhauled.
 Double boiler in good order - crown stays renewed - safety valve overhauled and adjusted to 70 lbs.
 Cylinders, pistons, slides pumps crank shaft & details examined and found in good order. Incocks & fastenings examined in dock & found good. For damage - Propeller broken in one blade and new propeller fitted, tail shaft good except after liner which was slack and a new one supplied & fitted.

General Observations, Opinion, and Recommendation:— The machinery of this vessel is now in good order & safe working condition & reliable in my opinion to remain as classed with the record L.M.C. 3-87 in the Register Book subject to the testing of the main boiler safety valves.

Office or Registration Fee (per Sec. 27)..... £ : :
 Survey Fee (per Section 28)..... £ 3 : 3 : 0
 Special on Damage, Fee (per Section 28)..... £ 1 : 1 : 0
 *Certificate (if required) to be sent as per margin.. £ : 5 : :
 Travelling Expenses (if chargeable)..... £ : : :
 received by me, 1887
 5/11/87

John H. Waller
 Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute FRIDAY 1 APRIL 1887

Assigned Note Safety valves



Form No. 9 - Registrar In-London - 1887

Insert Character of Ship and Machinery precisely as in the Register Book.

LON 680-0221

It is submitted that this vessel is eligible to have the notification No 3.87 recorded when the main boiler safety valves have been tested.

W.P.

23/3/87



© 2021

Lloyd's Register
Foundation