

Report of Survey for Repairs, &c., of Engines & Boilers.

No.

No. in
Reg. Book.

Survey held at *Nicholson's Wharf London*

Date, first Survey

8th Feb 1888

Last Survey

THURS 9

FEB 1888

188

Year

Month

4

on the Machinery of the

S.S. "J. J. Barry"

(Number of Visits

1

Year

Month

Tonnage, Gross

867

Built at

Middlesbrough

When built

1872

Ditto, Net

545

Owners

Harris & Dixon

Port belonging to

London

Diameter of Cylinder

27 1/2 x 33

Engines made by

J. Brassey & Co. B'head

When made

1872

Length of Stroke

33 ins

Boilers made by

" " " "

When made

"

Pressure of Steam

65

If Surveyed Afloat or in Dry Dock

Afloat

Classed *IMC 10. 85*

Registered Horse Power

99

B.S. 10. 87

Last Survey No.

Port

Particulars of Repairs and Examination

(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

Expiry of three months limit on the crank shaft, on account of crack in forward crank pin.

Examined the forward crank pin & found a circumferential crack round the pin near the after fillet, more than half way round.

Recommended that the new shaft which is now on board should be fitted on the vessel's arrival at Cardiff to which port she proceeds from London.

*For the Cardiff Surveyor
D.F. 9/2/88*

General Observations, Opinion, and Recommendation:—

(State clearly what alteration, if any, is suggested to be made in the existing notification of the vessel's machinery in the Register Book, consequent upon this survey.)

The machinery of this vessel as far as seen is in good condition & in my opinion the vessel should be allowed to remain as classed on condition that the new crank shaft be fitted on the vessel's arrival in Cardiff.

Survey Fee (per Section 28)

£

Special Damage Fee (per Section 28)

£

*Certificate (if required)

£

Travelling Expenses (if chargeable)

£

received by me,

188

Committee's Minute


FRIDAY 10 FEB 1888

TUESDAY 23 FEB 1888

Assigned

Deferred - write off 10/2/88

Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.



Lloyd's Register
Foundation