

REPORT of SURVEY for REPAIRS, &c.

No. 49534

Port of London

Received in London Office,

FRIDAY 31 MAY 1889

No. in Reg. Book.

Survey held at

Date, First Survey

Last Survey

24th Apr 30th May 1889

(No. of Visits)

Master J. R. Rennie

TONNAGE:—

NET

848

Built at

London

By whom

J. R. Rennie

When

1889

MONTH.

GROSS

848

Owners

Devitt Thorne

Port belonging to

London

UNDER DK.

782

Owners' Address

(if not already recorded in Appendix to Register Book.)

If Surveyed Afloat

In Dry Dock

Name of Dock

Green's

Destined Voyage

Adelaide

Length of Poop

ft.:

of Forecastle

ft.:

of Raised Qr. Deck

ft.:

Moulded Depth

ft.

ins.

(if these particulars are not yet recorded in the Register Book.)

Years assigned, if a Wood Ship.

Character in Register Book.

Last Survey, No.

48244

Port

Lon

Classed

S.S. Lon No 3. 10 76

*A 1

488

(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and Initials of any letters respecting this case.)

Society's Freeboard

in Summer

ft.

ins.

as painted on Ship

in Winter

ft.

ins.

REPAIRS, OR EXAMINATION AS PER RULE, FOR

S.S. No 3

All the close caulking removed. Floors, frames &c. chipped and Examined which with the cement found in good condition free peck cleared & Examined. Plating drilled and the measurements thereof found highly satisfactory. Vessel placed in dry dock. Bottom cleaned and painted. 2 new pintles to the Rudder. Mast and spars Examined. Chain Cables ranged and the deficiency as per wear supplied as follows.

90 fms 1 1/2 " No 3221 Test 57 1/2 and 7 3/4 tons Cheever Cable Machine 13th Feb^y 1882. A. J. Jack Sup^y.

Ridless linings stripped and the main piece found defective now renewed with English Oak and the spindle also new.

PRESENT CONDITION OF THE

| | | | | | | | | |
|------------------------------|------|----------------------------------|------|-------------------------------------|------|----------------------------|--------|--------------|
| Decks | Good | Plank (Bottom) & Counter | Good | Ceiling | Good | Boats | 4th | Good |
| Waterways | --- | Trunnels or Rivets | --- | Rudder | --- | Masts, Yards, &c. | --- | --- |
| Comings | --- | Breasthooks & Stems | --- | Windlass & Capstan | --- | Condition, how ascertained | --- | --- |
| Up'r Dk. Beams & Fastenings | --- | Transoms, Pointers, & Crutches | --- | Pumps | 2th | Sails | --- | --- |
| Low'r Dk. Beams & Fastenings | --- | Timbers of Frame at the openings | --- | Cement (if Iron Ship) | --- | Anchors | No. of | 10. 15 & 2th |
| Planksheers | --- | Ditto ditto at other places | --- | Caulking of Bot'm, D'k, & Wat'rways | --- | Cables | --- | --- |
| Sheerstrakes | --- | Keelsons | --- | Copper, or Y.M. (State if on Felt.) | --- | Hawsers & Warps | 3th | Good |
| Topsides | --- | Clamps & Chocks | --- | When put on | --- | Standing & Running Rigging | --- | --- |
| Wales | --- | Coal Bunker, Openings, Lids, &c. | --- | Scuppers | Good | Hatches | Good | Good |
| Engine Room Skylights | --- | | | | | | | |

General Observations, Opinion as to Class, Recommendation, &c.:

She is now in good and efficient condition eligible in our opinion to continue as classed and to have S.S. Lon No 3. 5-89 recorded in the Register Book

| | | | | |
|--|---|---|---|----|
| Entry Fee (if chargeable) per Scale I., Sec. 27... | £ | 5 | : | 0 |
| Office Fee (if chargeable) per Scale II., Sec. 27... | £ | : | : | : |
| Survey Fee (per Section 28) | £ | 5 | : | 5 |
| Special on Damage, Fee (if any) (per Sec. 28) .. | £ | : | : | : |
| *Certificate (if required) to be sent as per margin | £ | - | : | 5 |
| Travelling Expenses (if chargeable) | £ | : | : | : |
| Spur | £ | : | : | : |
| Second Surveyor's Fee (if any) | £ | : | : | 10 |
| | £ | : | : | 6 |

alc 5/6/89

Fees received by me.

7/6 1889

CHAS

Wm. B. Davy

Geo. W. Morper

Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute

TUES 4 JUNE 1889

Character assigned

*A 1

SS No 3-5789



Lloyd's Register Foundation