

REPORT of SURVEY for REPAIRS, &c.

No. 219 Date of Writing Report 18 Port of London Date, First Survey 5th April Last Survey 17th April 1890

No. in Reg. Book. 219 on the Iron Screw Steamer "El Dorado" Built at North Shields By whom T & W. Smith. When 1882

TONNAGE: - NET 833 864 GROSS 1298 1343 UNDER DK. 1111 Owners' Address El Dorado S.S. Co. (L) (Scrutton L. & Co.) Port belonging to London. Destined Voyage West Indies.

Last Survey, No. 21222 Port London L.M. 3.87 138 12.88 S.S. Lon. No. 1-87. 6.89

REPAIRS, OR EXAMINATION AS PER RULE, FOR Condition

This vessel has been placed in dry dock. The bottom examined & is in good condition. Puntles of rudder bushed. The top of boiler casing above bridge renewed with 7/16" plating - and on the starboard side the casing doubled with plating 11 ft. long, 15" deep & 3/8" thick - a length of angle iron 13 ft - worked on tie plate against the casing - and the angle iron at upper part of casing renewed - also three planks of bridge deck new on the starboard side against boiler casing & two against engine room casing.

PRESENT CONDITION OF THE		Plating		Boats	
Decks	good	Plank (Bottom) & Counter	good	Masts, Yards, &c.	good
Waterways	do	Treenails or Rivets	do	Condition, how ascertained	from deck
Comings	do	Breasthooks & Stemson	not exam'd	Sails	part seen - good
Up'r Dk. Beams & Fastenings	do	Transoms, Poiners, & Crutches	do	Anchors	No. of 3 B. 1 L. 2 K.
Low'r Dk. Beams & Fastenings	do	Timbers of Frame at the openings	good	Cables	part seen - good
Plank sheers	do	Ditto ditto at other places	not exam'd	Hawsers & Warps	good
Sheerstrakes	do	Keelsons	good	Standing & Running Rigging	do
Topsides	do	Clamps & Shells	do	Hatches	do
Wales	do				
Engine Room Skylights	do	Coal Bunker, Openings, Lids, &c.	do	Scuppers	good
				Cargo & Main Hatchways	good

General Observations, Opinion as to Class, Recommendation, &c.: This vessel appears to be eligible to remain as classed, and to have record of survey 4.90

Entry Fee (if chargeable) per Scale I., Sec. 27...	£	:	:	Fees applied for,
Office Fee (if chargeable) per Scale II., Sec. 27...	£	:	:	
Survey Fee (per Section 28)	£	0	0	18
Special on Damage, Fee (if any) per Sec. 28) ...	£	:	:	Received by me,
*Certificate (if required) to be sent as per margin	£	:	:	
Travelling Expenses (if chargeable)	£	:	:	18
Second Surveyor's Fee (if any)	£	:	:	

Committee's Minute FRIDAY 2 MAY 1890 Character assigned 100A1 BS 4/90

Form No. 2 for Repairs - 1000 - 13/8/89 - Transfer Int. - T. & S. The Surveyors are requested not to write on or below the space for Committee's Minute.

Insert Character precisely as in Register Book.

