

# REPORT of SURVEY for REPAIRS, &c.

No. 228 Date of Writing Report 18 Port of London Received in London Office, 8<sup>th</sup> MAR 1891  
 No. in Reg. Book 228 Survey held at London Date, First Survey 5<sup>th</sup> March Last Survey 13<sup>th</sup> March 1891  
 on the S.S. Caroline (No. of Visits 3) Master J. Scott Russell H. YEAR. MONTH.  
 TONNAGE:— NET 248 GROSS 466 UNDER DK. 425 Built at London By whom J. Scott Russell H. When 1853  
 Owners Toller & Son Port belonging to London

Owners' Address London  
 If Surveyed Afloat or in Dry Dock London Name of Dock Fountain Destined Voyage   
 Length of Poop  ft.: of Forecastle  ft.: of Raised Or. Deck  ft.: Moulded Depth  ft. ins.  
 (if these particulars are not yet recorded in the Register Book.)

Last Survey, No. 7435 Port Hull L.M.C. 2.89 13.5.90 Classed 85A.1  
 (State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Society's Freeboard (if assigned) in Summer ft. ins. as painted on Ship in Winter ft. ins.)

REPAIRS, OR EXAMINATION AS PER RULE, FOR Damage Repair

This vessel is stated to have been in collision & to have thereby received damage to the stem and two plating which have been repaired as follows:—  
 New upper piece of stem scarfed & fitted. Bow plate and doubling thereto in sheer strake & two plate in each of the two strakes next below the sheer strake on each side of the vessel—being six plates & two doubling plates in all—renewed. New ke plate to forward pair of frames fitted, & the pocket filled with cement.

PRESENT CONDITION OF THE		Plank (Bottom) & Counter	Ceiling	Boats
Decks	<u>gnd</u>	<u>pl seen</u> <u>gnd</u>	<u>pl seen</u> <u>gnd</u>	<u>gnd</u>
Waterways	<u>4</u>	<u>pl seen</u> <u>gnd</u>	<u>4</u>	<u>gnd</u> <u>as seen</u>
Comings	<u>4</u>	<u>4</u>	<u>Windlass &amp; Capstan</u>	<u>Condition, how ascertained</u> <u>from deck</u>
Up'r Dk. Beams & Fastenings	<u>pl seen</u> <u>4</u>	<u>Transoms, Pointers, &amp; Crutches</u> <u>pl seen</u>	<u>Pumps</u> <u>4</u>	<u>Sails</u> <u>Complete</u>
Low'r Dk. Beams & Fastenings	<u>4</u> <u>4</u>	<u>Transoms of Frame at the openings</u> <u>gnd</u>	<u>Cement (if Iron Ship)</u> <u>pl seen</u>	<u>Anchors</u> <u>No. of</u> <u>4</u>
Plank sheers	<u>4</u>	<u>Ditto ditto at other places</u> <u>4</u>	<u>Caulking of Bot'm, D'k, &amp; Watrways</u> <u>gnd</u>	<u>Cables</u> <u>pl seen</u> <u>Complete</u>
Sheerstrakes	<u>Plating</u> <u>gnd</u>	<u>Keelsons</u> <u>pl seen</u>	<u>Copper, or V.M.</u> <u>(State if on felt.)</u> <u>When put on</u>	<u>Hawser &amp; Warps</u> <u>gnd</u>
Topsides	<u>4</u>	<u>Clamps &amp; Shells</u> <u>gnd</u>	<u>Scuppers</u> <u>gnd</u>	<u>Standing &amp; Running Rigging</u> <u>4</u>
Wales	<u>4</u>	<u>Coal Bunker, Openings, Lids, &amp;c.</u> <u>gnd</u>	<u>Cargo &amp; Main Hatchways</u> <u>gnd</u>	<u>Hatches</u> <u>4</u>
Engine Room Skylights	<u>gnd</u>			

General Observations, Opinion as to Class, Recommendation, &c.:

This vessel appears to be in gnd condition & is eligible, & my opinion to remain as classed with record of survey 3.91

Entry Fee (if chargeable) per Scale I., Sec. 27...	£	:	:	
Office Fee (if chargeable) per Scale II., Sec. 27...	£	:	:	
Survey Fee (per Section 28).....	£	:	:	
Special on Damage, Fee (if any) (per Sec. 28)....	£	2	:	2
*Certificate (if required) to be sent as per margin	£	2	:	2
Travelling Expenses (if chargeable) .....	£	2	:	2
Second Surveyor's Fee (if any) .....	£	:	:	

Fees applied for, 24/3/91  
 Received by me, 7.12.1891

Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute THURS. 26 MAR 1891  
 Character assigned 85A.1