

# REPORT of SURVEY for REPAIRS, &c.

No.

Date of Writing Report

28 aug

1891

Port of London

Received in London Office,

SAT, 29 AUG 1891

No. in Reg. Book.

Survey held at

London

Date, First Survey

15 Aug

Last Survey

27 Aug

1891

148

on the

London S.S. El Dorado

Master

Smith

YEAR.

MONTH.

TONNAGE:-

NET

820

GROSS

1291

UNDER DK.

1059

Built at

R. Shields

By whom

J. W. Smith

When

1882

7

Owners

El Dorado S.S. Co.

Port belonging to

London

Owner's Address

(if not already recorded in Appendix to Register Book.)

Hertham Lane Co.

If Surveyed Afloat or in Dry Dock

Name of Dock

Know Dry Dock

Destined Voyage

West Indies

Length of Poop

ft.: of Forecastle

ft.: of Raised Or. Deck

ft.: Moulded Depth

ft.

ins.

(if these particulars are not yet recorded in the Register Book.)

Years assigned, if a Wood Ship.

Character in Register Book.

Classed

+Inc-1191

100 A1-4.90

Last Survey, No.

57423

Port

London

(State clearly the cause of Repairs if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Society's Freeboard Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and Initials of any letters respecting this case.)

REPAIRS, OR EXAMINATION AS PER RULE, FOR Completion S.S. No 3

In the hold the close ceiling at the bow of the barge removed, surfaces cleaned and recoated and ceiling replaced.

In the fore hold on the Starboard side four bracket plates connecting the web frames to tank top found cracked now renewed, and also one plate in the after hold Starboard side.

In the machinery space, four floors under the boiler doubled between the side stringers, five floors under the stokehold fitted with doublings at the centre line on both sides; the side stringer angle iron and five reverse frames under the boiler renewed; and nine intercostal wash plates on each side doubled, the doublings being connected to outside plating. The bridge deck with the exception of the outer margin planks has been renewed. Panelling removed from under side lights in the bridge and saloon, plating in good order cleaned and recoated.

Mast and spars examined and mainmast renewed, & rigging overhauled. Bottom examined in good condition cleaned and recoated.

PRESENT CONDITION OF THE

Decks	Good	Plank (Bottom) & Counter	Good	Ceiling	Good	Boats	Good
Waterways	"	Treemalls or Rivets	"	Rudder	rebrashed	Masts, Yards, &c.	"
Comings	"	Breasthooks and Stemson	"	Windlass & Capstan	"	Condition, how ascertained	alop
Up'r Dk. Beams & Fastenings	"	Transoms, Pointers, & Crutches	"	Pumps	"	Sails	not seen
Low'r Dk. Beams & Fastenings	"	Timbers of Frame at the openings	"	Cement (if Iron Ship)	"	Anchors	No. of 33. 15 2K
Planksheers	"	Ditto ditto at other places	"	Caulking of Bot'm, D'k, & Watrways	"	Cables	not seen good
Sheerstrakes	"	Keelsons	"	Copper, or Y.M.	"	Hawsers & Warps	"
Topsides	"	Clamps & Shelves	"	(State if on Felt.)	"	Standing & Running Rigging	"
Wales	"			When put on	"		

Engine Room Skylights " Coal Bunker, Openings, Lids, &c. " Scuppers good Cargo & Main Hatchways good Hatches "

General Observations, Opinion as to Class, Recommendation, &c.: This vessel being now in a good and efficient condition she is eligible in my opinion to remain as classed and to have recorded S.S. No 3. -91 and new date of 8, 91

Entry Fee (if chargeable) per Scale I., Sec. 27..	£	:	:
Office Fee (if chargeable) per Scale II., Sec. 27..	£	:	:
Survey Fee (per Section 28) .....	£	4	:
Special on Damage Fee (if any) (per Sec. 28)....	£	:	:
*Certificate (if required) to be sent as per margin	£	:	:
Travelling Expenses (if chargeable) .....	£	:	:
Second Surveyor's Fee (if any) .....	£	:	4.6

Fees applied for,

24/8 1891

Received by me,

4.9 18 91

Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute

Character assigned

100 A

SS No 3-8/91

ROBERT EDMUND TAYLOR & SON, Commercial Steam Printers, 19, Old Street, Goswell Road, London.

No 3.

LON 694-0064

State if a Report is also sent on the Machinery of the Ship

Certificate to be sent to

Form No. 2 for Repairs-10000-6/31-Transfer Ink-J & S. The Surveyors are requested not to write on or below the space for Committee's Minute.

Insert Character precisely as in Register Book.