

REPORT of SURVEY for REPAIRS, &c.

Date of writing Report 18. When handed in at Local Office 18. Port of WED. 10 FEB 1892
 No. in Reg. Book 117 Survey held at London Date, First Survey January 22nd Last Survey 3rd February 1892
 on the S.S. Deerhound (No. of Visits) 5 Master G. Smith

TONNAGE:— Built at London By whom Forrest Hm When 1882 10
 GROSS 443 Owners Walker Howard H. Port belonging to London
 UNDER DK. 329 Owners' Address
 NET 271 (if not already recorded in Appendix to Register Book.)

Surveyed Afloat or in Dry Dock? Afloat Name of Dock Fountain Destined Voyage
 WB=DBa tons; f tons; u&B tons; CellDB tons; Particulars of Classification (which must be inserted precisely as in Register Book & Supplements).
 FPT tons; APT tons; MT tons.

1st Survey, No. 51155 Port London

Periodical Surveys, when held, must be reported in detail and seriatim in the terms of the Rules. State clearly the cause of Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; and besides being detailed in the body of the report, should be summarised in the form shown below. Whenever the replacement of Anchors or Chains is reported, the particulars of weight or size and test of the articles should be clearly stated, and also the weight or size, &c., required by the Rules, together with the vessel's Equipment Letter, if any. State also the dates and initials of any letters respecting this case.

REPAIRS, OR EXAMINATION AS PER RULE, FOR Damage Repair

This vessel is stated to have been in collision with the S.S. "Ebro" & to have received damage to the starboard quarter abreast the after hatchway. Repairs to this damage have now been done as under: Two plates in quarter deck side renewed, two frames in way of same part renewed, & two others doubled: one plate on quarter deck stump renewed, & one taken out faired & re-rigged; the plate on each side in way of hatchway faired; bulwarks & rails made good; angle iron casing on starboard side of after hatchway renewed & the half beams refastened. Deck plank & waterways removed for these repairs now relaid, part being renewed on account of damage, & recaulked.

SUMMARY OF DAMAGE REPAIRS:— Plates, Faired or Repaired: 2 Frames, ditto. 3 Plates, Renewed; 2 Frames, ditto. Other Repairs: pl. on deck & waterways

PRESENT CONDITION OF THE							
Decks	grd	Transoms, Pointers, & Crutches	not seen	Copper, or Y.M.	—	Hatches	grd
Waterways	"	Timbers of Frame at the openings	"	(State if on Fell.)	—	Boats	"
Oramings	"	Ditto ditto at other places	"	When put on, Month	— Year	Masts, Yards, &c.	grd as seen
Up'r Dk. Beams & Fastenings	pl. seen	Keelsons	not seen	Rudder	not seen	Condition, how ascertained	from deck
Low'r Dk. Beams & Fastenings	pl. seen	Clamps, Shells & Stringers	pl. seen	Windlass & Capstan	grd	Sails	grd
ing	pl. seen	Salting	—	Pumps	"	Anchors No. of	complete
Planking	—	Ceiling	pl. seen	Engine Room Skylights	"	Cables, length	not seen
Transoms or Rivets	pl. seen	Cement or Asphalt	not seen	Coal Bunker, Open'gs, Lids, &c.	"	(State if now ranged)	—
Breasthooks & Stemson	not seen	Tanks	do	Scuppers	"	Hawsers & Warps	grd
		(State if now tested.)	—	Cargo & Main Hatchways	"	Standing & Running Rigging	—
		Caulking of Bottom, Dk. & Wat'rways	grd				

General Observations, Opinion as to Class, Recommendation, &c.:

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:—"to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey, 9,91," or "to remain as classed and to have record of survey, 9,91, and the notations of ss No. 1-91 and ptND91, &c."

The above repairs have been satisfactorily done & as far as seen the vessel is in good condition & eligible in my opinion to remain as classed; but with no alteration in date of last survey.

Office Fee (if chargeable) per Scale II, Sec. 27	£	:	:	Fees applied for,
Survey Fee (per Section 28)	£	:	:	13/21 1892
Special Damage or Repair Fee (if any) (per Sec. 28.)	£	2	2	Received by me,
Travelling Expenses (if chargeable)	£	:	:	16/21 1892
Second Surveyor's Fee (if any)	£	:	:	—
Is Certificate now required?				

Committee's Minute

Character assigned

TUES. 16 FEB 1892

100A1

as now

Surveyor to Lloyd's Register of British & Foreign Shipping.



© 2019

Lloyd's Register Foundation

LON695-0229