

52729. For

ring $4" \times 3" \times \frac{7}{16}"$, supported by two hinges with oval
holes in way of pin in order that the door may be opened
equally home by means of two strong backs.

Compensation is provided by working two angle bars
over ports attached to the reverse frames $5 \times 4 \times \frac{9}{16}$ with
 $\frac{1}{2}$ plate between them attached to the shell by
 $3\frac{1}{2} \times 3\frac{1}{2} \times \frac{1}{2}$ angles extending for two frames before the port
to two frames abaft

S. J. Turney