

REPORT of SURVEY for REPAIRS, &c.

Date of writing Report 23/3/92 When handed in at Local Office 23/3/92 Port of London T. IRS. 24 MAR 1892No. in Reg. Book. 1574 Survey held at London Date, First Survey 15th March Last Survey 21st March 1892
on the "Remus" Steel Screw By whom W. Gray & Co. Master Simpson 1892TONNAGE:— Built at W. Harlepool Owners C. Andersen Port belonging to Hamburg
GROSS 2635
UNDER DECK 2041NET 1722 Owners' Address R. & W. Green Destined Voyage Hamburg
Surveyed Afloat or in Dry Dock? By R. & W. Green Name of Dock R. & W. GreenWB=DBa tons; f tons; uE&B tons; Cell DB 624 tons; }
FPT tons; APT tons; MT tons. }Last Survey, No. 533 Port Eng +100 A.I. +100 C 12/89
Well ok. 8/90

(Periodical Surveys, when held, must be reported in detail and serially in the terms of the Rules. State clearly the cause of Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; and besides being detailed in the body of the report, should be summarised in the form shown below. Whenever the replacement of Anchors or Chains is reported, the particulars of weight or size and test of the articles should be clearly stated, and also the weight or size, &c., required by the Rules, together with the vessel's Equipment Letter, if any. State also the dates and initials of any letters respecting this report.)

REPAIRS, OR EXAMINATION AS PER RULE, FOR Damage Repairs (Condition)

In consequence of damage caused by collision

This vessel was placed in dry dock, the bottom examined cleaned & coated, Rudder lifted & the pulleys bushed.

On the Port Side at fore end of Bridge. 2 Bridge Plank Make plates renewed and one in next make below. Five frames partly renewed & butts compensated for by fitting back iron 4 feet long, the butts being well shifted. Two Bridge Deck Stringer plates renewed. also lead iron & strappings trails in wake of damage. The deck matted to ascertain its efficiency.

SUMMARY OF DAMAGE REPAIRS:— Plates, Faired or Repaired:— Frames, ditto. 5 Plates, Renewed: 5 Frames, ditto. Other Repairs 7 Bridge Deck beams renewed

PRESENT CONDITION OF THE		Good		Good		Good	
Decks		Transoms, Pointers, & Girders		Copper, or I.M.		Hatches	
Waterways		Timbers of Frame at the openings		(State if on Feet.)		Boats	
Coamings		Ditto ditto at other places		When put on, Month		Masts, Yards, &c.	
Up'r Dk. Beams & Fastenings		Keelsons		Rudder		Condition, how ascertained	
Low'r Dk. Beams & Fastenings		Clamps, Shells & Stringers		Windlass & Capstan		Sails	
Plating		Salting		Pumps		Anchors No. <u>310, 18.2K</u>	
Decking		Ceiling		Engine Room Skylights		Cables, length <u>stated complete</u>	
Transverse Rivets		Cement or Asphalt		Coal Bunker, Open'gs, Lids, &c.		(State if now rammed or cauged)	
Breasthooks & Stowage		Tanks <u>not tested</u>		Scuppers		Hawsers & Warps <u>sufficient</u>	
		Caulking of Bot'm, D'k, & Wat'rw'ys		Cargo & Main H'tch'w'ys		Standing & Running Rigging <u>good</u>	

General Observations, Opinion as to Class, Recommendation, &c.:—

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:—"to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey, 9,91," or "to remain as classed and to have record of survey, 9,91, and the notations of ss. No. 1-91 and ptND91, &c."

This vessel now appears to be in a sound & efficient condition, eligible in our opinion to remain as classed with a fresh record of Survey Lon 3/92.

Office Fee (if chargeable) per Scale II., Sec. 27 £

Survey Fee (per Section 28) £

Special Damage or Repair Fee (if any) (per Sec. 28.) £ 4

Travelling Expenses (if chargeable) £

Second Surveyor's Fee (if any) £

*Is Certificate now required?

Fees applied for, 20/3/18.92Received by me, Surveyor to Lloyd's Register of British & Foreign Shipping

Committee's Minute

Character assigned

FRI 25 MAR 1892



© 2019

Lloyd's Register Foundation

LON695-0403