

No. 53804

REPORT of SURVEY for REPAIRS, &c.

Survey held at	<u>London</u>	Date, First Survey	<u>Oct 20th 1892</u>	Last Survey	<u>Oct 22 1892</u>
on the Wood, Iron or Steel	<u>S.S. "Panama Castle"</u>	(No. of Tons)	<u>2580</u>	Master	<u>J. Lafiero</u>
VNAGE:		YEAR.		MONTH.	
<u>2580</u>					
<u>1652</u>					
<u>2382</u>					
Owners' Address	<u>Italia Britannica Royl Yacht Lin</u>				
(if not already recorded in Appendix to Register Book.)					
ed Afloat or in Dry Dock?	<u>Afloat</u>	Name of Dock	<u>Union</u>	Destined Voyage	<u>Naples</u>

Ba tons; f tons; uE&B tons; CellDB tons; FPT tons; APT tons; MT tons.

N.B.—All alterations in the existing records should be underlined.

Survey, No. 9873 Port Off

Surveys, when held, must be reported in detail and serially in the terms of the Rules. State clearly the parts, if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; being detailed in the body of the report, should be summarised in the form shown below. Whenever the state of Anchors, Chains, or Hawsers is reported, the particulars of weight or size and test of the articles clearly stated, and also the weight or size, &c., required by the Rules, together with the vessel's Equipment.

State also the dates and initials of any letters respecting this case.

OR EXAMINATION AS PER RULE, FOR

revel placed on the walls in dry dock, & the bottom
amidst, & the following plates found to be slightly indented,
though the Cap't states that he has no knowledge of the
vessel having touched the ground.—

Port side

90° 8, 11+12 plates in A strake indented (garboard strake)
 " 2, 10, 11+12 " " B " "
 " 2, 8, 9+10 " " C " "

Starboard side

90° 15° - - - plate in A strake indented (garboard strake)
 " 15° - - - " " B " "

" tanks were full of water & the bottom was tight; they were

DAMAGE REPAIRS: Plates, Fair'd or Repaired; Frames, ditto; Plates, Renewed; Frames, ditto. Other Repairs.

EDITION OF THE

Good

Transoms, Bulkheads, & Guttels	<u>Not seen</u>
Timbers of Frame at the openings	<u>Good</u>
Bon't ditto at other places	"
Keelsons	"
Clamps, Shaf'ts, & Stringers	"
Salting (State if examined.)	"
Ceiling	"
Generators Asphalt (State which)	"
Tanks	<u>Not tested</u>
Caulking of Bot'm, D'k, & Wat'rwy's	"

Copper, or Y.M. (State if on Felt.)	<u>✓</u>
When put on, Month	<u>✓</u>
Year	"
Rudder	<u>Good</u>
Windlass & Capstan	"
Pumps	"
Engine Room Skylights	"
Coal Bunker, Open'gs, Lids, &c.	"
Scuppers	"
Cargo & Main H'tehw'y's	"

Hatches	<u>Good</u>
Boats	"
Masts, Yards, &c.	"
Condition, how ascertained	<u>from all said to be good</u>
Sails	<u>said to be good</u>
Equipment letter	"
Anchors, No. of	<u>300-16-216</u>
Cables (State if now ranged)	<u>30</u>
" length	" size
" Rule length	" size
Hawsers & Warps	<u>good</u>
Standing & Running Rigging	"

General Observations, Opinion as to Class, Recommendation, &c.:

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:—"to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey, 9,91," or "to remain as classed and to have record of survey, 9,91, and the notations of ss No. 1-91 and ptND91, &c."

This vessel appears to be in good condition (with the exception of the damage stated above, which has been temporarily repaired.) It is submitted that she is eligible to remain as classed, subject to the permanent repairs being executed on her return to this country, as per attached letter from the owners, dated the 2nd Nov 1892.

Fee (if chargeable) per Scale II, Sec. 27 £ : :

Fee (per Section 28) £ : :

al Damage or Repair Fee (if any) £ : :

ing Expenses (if chargeable) £ : :

ed Surveyor's Fee (if any) £ : :

Certificate now required?

nmittee's Minute

aracter assigned

Fees applied for,

3/11/1892

Received by me,

10/11/1892

1892

Surveyor to Lloyd's Register of British & Foreign Shipping.

TUES. 28 FEB 1893

TUES. 13 DEC 1892 2019

Deferred for
lloyd's Register
Foundation

LONGFORD-0269

FRI 4 NOV 1892

Deferred for
perm't repair

W. White (Signature)

d. White (Signature)

53807 L.W.

were afterwards emptied, & the condition of the asphalt & frame
inside examined, as far as practicable.—

The owners stated, that having a contract with the State
Government, it would be exceedingly inconvenient to
permanently repair this damage now, & in consequence
temporary repairs have been effected as follows.—

The rivets removed where necessary, & portions of the seam
caulking made good.— Covering plates fitted over the
indentations to the shell, one forward, & one amidships
on the port side.—

The bottom has been cleaned & painted.—

Franklin Wilson

Geo T. Cooper

N.B.—If this Report is copied by Copying Press, especial care must be taken that the copying paper is not so much damped as to spread the ink, or cause it to show through to the other side.

23 DIC 1892



© 2019

Lloyd's Register
Foundation