

REPORT of SURVEY for REPAIRS, &c.

Date of writing Report Oct 28th 1893 When handed in at Local Office

18

Port of London

No. in Survey held at London Date, First Survey Sep 17th 1893 Last Survey Oct 26th 1893.
 Reg. Book. on the Wood, Iron or Steel Bk. "Don" (No. of Visits) Tens
 430 Built at H. Glasgow By whom Russell & Co. Master J. Sinclair
 GROSS 1168 Owners F. MacFarlane Port belonging to H. Glasgow
 UNDER D.K. 1070 Owners' Address MacFarlane (his office at head of Rpt on the Doc & min.)
 NET 1115
 Surveyed Afloat or in Dry Dock? Name of Dock Cubitt Town dry dock Destined Voyage Brisbane
 WB=DBa tons; F PFT tons; uE&B tons; CellDB tons; MT tons.

N.B.—All alterations in the existing records should be underlined.

Last Survey, No. 53038 Port LON

(Periodical Surveys, when held, must be reported in detail and seriatim in the terms of the Rules. State clearly the cause of Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; and besides being detailed in the body of the report, should be summarised in the form shown below. Whenever the replacement of Anchors, Chains, or Hawser is reported, the particulars of weight or size and test of the articles should be clearly stated, and also the weight or size, &c., required by the Rules, together with the vessel's Equipment Letter, if any. State also the dates and initials of any letters respecting this case.

CHARACTER.	Years Assigned or required.	Machinery and Boiler Surveys (including date of N.B., if any).
✓ for Special Survey. Date of last Survey and of Periodical Surveys.		
- 100 A.I. 5.92 S.S. Lon. N° 1. 89		

Society's Freeboard (if assigned) as painted on Ship and now verified 14 ft. 4 ins.

REPAIRS, OR EXAMINATION AS PER RULE, FOR Part S.S. N° 2.

The vessel placed in dry dock, the bottom examined, scaled & painted. The rudder lifted & rebushed; The hold cleared from collision bulkhead to 8ft forward of fore end of main hatch & from after part of fresh water tanks to stern post. all the timber boards, ceiling hatches & ceiling in excess of the rule requirements lifted at these parts and the iron work scaled & cement washed & the cement in the bottom examined. The tween decks cleaned & painted fore & aft. The fore peak and lazarette cleared, examined & recoated. The decks examined & a few planks renewed.

The chain cables runged and the windlass, masts, spars and general equipment examined.

Fore topmast renewed.

To complete S.S. N° 2: The hold from after part of water tanks to 8ft forward of fore end of main hatch requires to be cleared & examined.

SUMMARY OF DAMAGE REPAIRS: Plates, Fairied or Repaired; Frames, ditto. Plates, Renewed; Frames, ditto. Other Repairs

PRESENT CONDITION OF THE

Decks	Good	Transoms, Pointers, & Crutches	Good	Copper, or Y.M. (State if on Belt.) ✓	Hatches	Good
Waterways	"	Timbers of Frame at the openings	"	When put on, Month ✓ Year ✓	Boats	"
Coamings	"	ditto ditto at other places	"	Rudder	Good	Masts, Yards, &c.
Up'r Dk. Beams & Fastenings	"	Keelsons	"	Windlass & Capstan	"	Condition, how ascertained by examination
Low'r Dk. Beams & Fastenings	"	Chains, Shells & Stringers	"	Pumps	"	Sails
Plating	"	Salting (State if examined.)	✓	Engine Room Skylights	✓	Equipment letter ✓
Planking	✓	Ceiling	Good	Coal Bunker, Open'gs, Lids, &c.	✓	Anchors, No. of 3 B.s 18" + 2 Kgs
Treenails or Rivets	Good	Gumet or Asphalt (State which.)	"	Scuppers	Good	Cables (State if now ranged) 7 nos ,, length 270 ft. mds, size 1 1/2"
Breasthooks & Stemson	"	Tanks (State if now tested.)	✓	Cargo & Main Hatchw'ys	"	,, Rule length 270 ft. size 1 1/2"
		Caulking of Bot'm, Dk, & Wat'rwy's	Good			Hawsers & Warps Good
						Standing & Running Rigging

General Observations, Opinion as to Class, Recommendation, &c.:—

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:—"to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey, 9/91," or "to remain as classed and to have record of survey, 9/91, and the notations of ss No. 1-91 and pnd 91, &c."

This vessel is now in good & efficient condition and in our opinion eligible to remain as classed and to have record of survey 10.93. in the Register Book and when the survey has been completed to have notation S.S. Lon. N° 2 - 93 recorded.

Office Fee (if chargeable) per Scale II, Sec. 27 2

Survey Fee (per Section 28) 2

Special Damage or Repair Fee (if any) 2

Travelling Expenses (if chargeable) 2

Second Surveyor's Fee (if any)

Fees applied for,

31.10. 1893

Received by me,

3/11. 18.93

J. H. Transcott

Surveyor to Lloyd's Register of British & Foreign Shipping.

*Is Certificate now required? Yes.

Committee's Minute

Character assigned

FRI 3 NOV 1893

100 A.I.

FRIDAY 3 NOV 1894

© 2019



Lon700 - 0242