

## REPORT of SURVEY for REPAIRS, &amp;c.

Date of writing Report 28<sup>th</sup> Nov. 1894 When handed in at Local Office

Port of London

No. in Survey held at London  
Reg. Book. 135 on the Wood, Iron or Steel S.S. "Malvern"Date, First Survey Nov 13<sup>th</sup> (No. of Visits) Last Survey 22<sup>nd</sup> Nov 1894

Master Hyde

YEAR. MONTH.

## TONNAGE:-

2493

Built at W. Hartlepool By whom D. Gray &amp; Co When 1890 6.

## Gross Tonnage

1988

Owners Galbraith Penrith &amp; Co Port belonging to London

## NET Tonnage

1628

Owners' Address

(If not already recorded in Appendix to Register Book.)

Surveyed Afloat or in Dry Dock? Name of Dock Green's Dry dock Destined Voyage Port Said via Cardiff

WB=DBa tons; f tons; uE&amp;B tons; CellDB tons; FPT tons; APT tons; MT tons.

## Particulars of Classification (which must be inserted precisely as in Register Book &amp; Supplements).

N.B.—All alterations in the existing records should be underlined.  
If the vessel has Water Ballast Tanks, state whether the manhole covers have been removed, and the insides of the tanks examined. Also state the amount of deterioration (if any) found in the thicknesses of the floors, framing, girders, and of the inner bottom plating, especially in the boiler space.

| CHARACTER.        | Years Assigned now expired. | Machinery and Boiler Surveys (including date of N.B., if any). |
|-------------------|-----------------------------|--|
| +100 A 1-<br>5.94 |                             | +Lm 6.90   |

Last Survey, No. 921

Port Bry

Periodical Surveys, when held, must be reported in detail and seriatim in the terms of the Rules. State clearly the cause of Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; and besides being detailed in the body of the report, should be summarised in the form shown below. Whenever the replacement of Anchors, Chains, or Hawser is reported, the particulars of weight or size and test of the articles should be clearly stated, and also the weight or size, &amp;c., required by the Rules, together with the vessel's Equipment Letter, if any. State also the dates and initials of any letters respecting this case.

Society's Freeboard (if assigned) as painted on Ship and now verified

REPAIRS, OR EXAMINATION AS PER RULE, FOR In consequence of grounding on an Holt Reef, and through collision with the tug "Don" in the River Thames Part Special Survey 9<sup>th</sup> 1.

Vessel placed in dry dock bottom examined cleaned and painted. Rudder lifted, the pintles rebushed and the steering gear overhauled.

The tanks and limbers all fore and aft cleaned out and the cement pumps &amp;c examined and found in good condition.

The above satisfies part of the requirements of S.S. 1<sup>st</sup> June 1894.

Damage through collision: - One plate on starboard quarter renewed how done, not for damage. The port and starboard hawse pipes repaired by fitting an additional casting outside under the

## SUMMARY OF DAMAGE REPAIRS:— Plates, Fairied or Repaired; Frames, ditto. / Plates, Renewed; Frames, ditto. Other Repairs.

## PRESENT CONDITION OF THE

|                              |          |                                     |          |                                     |                    |                    |                              |
|------------------------------|----------|-------------------------------------|----------|-------------------------------------|--------------------|--------------------|------------------------------|
| Decks                        | Good     | Transoms, Beams, & Crutches         | Not seen | Copper, or Y.M. (State if on Felt.) | When put on, Month | Year               | Hatches                      |
| Waterways                    | "        | Timbers of Frame at the openings    | Good     | "                                   | "                  | "                  | Boats                        |
| Coamings                     | "        | Brace ditto at other places         | "        | Budder                              | Good               | "                  | Masts, Yards, &c.            |
| Up'r Dk. Beams & Fastenings  | "        | Keelsons                            | "        | Windlass & Capstan                  | "                  | "                  | Condition, how ascertained   |
| Low'r Dk. Beams & Fastenings | "        | Clamps, Shells & Stringers          | "        | Pumps                               | "                  | "                  | Sails                        |
| Plating                      | "        | Salting (State if examined.)        | "        | Engine Room Skylights               | "                  | "                  | Equipment letter             |
| Planing                      | "        | Ceiling                             | "        | Coal Bunker, Open'gs, Lids, &c.     | "                  | "                  | Anchors, No. of              |
| Teaknails or Rivets          | "        | Cement or Asphalt (State which.)    | "        | Scuppers                            | "                  | "                  | Cables (State if now ranged) |
| Breasthooks & Stemson        | Not seen | Tanks (State if now tested.)        | "        | Cargo & Main H'tch'ys               | "                  | "                  | length size                  |
|                              |          | Caulking of Bot'm, D'k, & Wat'rwy's | Good     |                                     |                    | " Rule length size | Hawsers & Warps              |
|                              |          |                                     |          |                                     |                    |                    | Standing & Running Rigging   |

## General Observations, Opinion as to Class, Recommendation, &amp;c.:—

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:—"to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey, 9/91," or "to remain as classed and to have record of survey, 9/91, and the notations of ss No. 1-91 and PTND91, &amp;c."

This vessel, so far as seen, is now in good and efficient condition and eligible in my opinion to remain as classed without record of survey.

|   |             |                   |
|---|-------------|-------------------|
| Office Fee (if chargeable) per Scale II., Sec. 27   | £ 0 : 0 : 0 | Fees applied for, |
| Survey Fee (per Section 28)                         | £ 0 : 0 : 0 | 29/11/1894        |
| Special Damage or Repair Fee (if any) (per Sec. 28) | £ 3 : 3 : 0 | Received by me,   |
| Travelling Expenses (if chargeable)                 | £ 0 : 0 : 0 | 30/11/1894        |
| Second Surveyor's Fee (if any)                      | £ 0 : 0 : 0 | 18/12/1894        |

\*Is Certificate now required?

Committee's Minute

Character assigned

FRIDAY 30 NOV 1894

Deferred for  
completo of No. 1E. B. Champneys  
Surveyor to Lloyd's Register of British & Foreign Shipping.

FRI 28 JUN 1895

TUES 2 JUL 1895

Lloyd's Register  
Foundation  
London - 0426 1/2

## Steel S. S. "Bralveru"

lower part of the ship

To complete the S. S. "Bralveru" the following remains to be done

- (1). The fore and after peaks to be cleared and examined.
- (2). The ceiling removed from the tank tops & the tanks tested by water pressure to the light line.
- (3). The holds and tween decks to be examined.
- (4). The coal bunkers to be cleared and examined and ceiling <sup>holds</sup> same lifted.
- (5). The shutes and watertight doors to be examined.
- (6). The masts & spars to be examined.
- (7). The steel upper deck to be scaled and recoated.

It is the intention of the owners to complete this survey upon the vessel's return from the present voyage.

E. B. Champness