

REPORT of SURVEY for REPAIRS, &c.

Writing Report 13<sup>th</sup> Dec 1894 When handed in at Local Office 18<sup>th</sup> Port of London  
Survey held at London Date, First Survey Nov 24<sup>th</sup> Last Survey 11<sup>th</sup> Dec 1894  
on the Wood, Iron or Steel S.S. "John M. Intyee" Master Johnson  
Tonnage:— Built at Newcastle By whom Palmers & Co When 1863 8  
DK 860 Owners C. F. Cory - Dright Port belonging to London  
573 Owners' Address  
Used in Dry Dock? Name of Dock Bridge Dry Dock Destined Voyage The Tyne  
DBa tons; f tons; uE&B tons; Cell DB tons; }  
FPT tons; APT tons; MT tons. }  
Particulars of Classification (which must be inserted precisely as in Register Book & Supplements).

N.B.—All alterations in the existing records should be underlined.  
the vessel has Water Ballast Tanks, state whether the manhole covers have been removed, and the insides  
examined. Also state the amount of deterioration (if any) found in the thicknesses of the floors, framing,  
and of the inner bottom plating, especially in the boiler space.  
Survey, No. 5593 Port London  
CHARACTER. \* for Special Survey. Date of last Survey and of Periodical Surveys. Years Assigned and expired. Machinery and Boiler Surveys (including date of N.B., if any).  
+ 90A. 1. 136.94  
6.94. Lmb 5.92  
S.S. Nov 23-5-92  
At 12/12/93  
Society's Freeboard (if assigned) as painted on Ship and now verified ft. ins.

IRS, OR EXAMINATION AS PER RULE, FOR of Damage through collision with the  
S.S. "Morthyr" in the River Thames.  
Vessel placed in dry dock.  
The stem plate in E and F strakes on  
inboard side and in E, F and G strakes on port side renewed,  
and that in G strake on starboard side cut out, faired and refitted.  
The foremost frame and reversed frame on each side and the  
reversed frame on port side part renewed; the foremost deep floor  
to renewed, two keelthwart plates cut out, faired & refitted,  
The fore part of main and fore-castle decks recaulked, & one  
hor stoke renewed.  
It is stated that a new bower anchor was placed on board in  
River before the vessel sailed but no opportunity has been  
ded to inspect this anchor, certificate of which is attached.

RY OF DAMAGE REPAIRS: — 1 Plates, Faired or Repaired; — Frames, ditto. 5 Plates, Renewed; 2 Frames, ditto. Other Repairs 3 reversed frame, part re-  
NT CONDITION OF THE  
Good Transoms, Pointers, & Crutches. Not seen Copper, or Y.M. Hatches Good  
ays " Timbers of Frame at the openings. Good (State if on Felt.) Boats " Year  
gs " Ditto ditto at other places. Not seen When put on, Month Rudder Good  
Beams & Fastenings " Keelsons Part seen. Good Windlass & Capstan " Condition, how ascertained From DK  
k. Beams & Fastenings " Clamps, Shelves & Stringers " Sails  
" Salting (State if examined.) Pumps " Equipment letter N  
" Ceiling " Engine Room Skylights " Anchors, No. of 2 B. 15. 2 K.  
" Cement or Asphalt. Not seen Coal Bunker, Open'gs, Lids, &c. " Cables (State if now ranged) No  
" Tanks (State if now tested.) Scuppers " " length size  
Books & Stowage " Caulking of Bot'm, D'k, & Wat'r'ys. Good Cargo & Main H'tch'ys. " Rule length size  
" Standing & Running Rigging " Hawsers & Warps Good

General Observations, Opinion as to Class, Recommendation, &c.:—  
State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon  
this survey, thus, for example:—"to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of  
Survey, 9,91," or "to remain as classed and to have record of survey, 9,91, and the notations of ss No. 1-91 and ptND91, &c."  
So far as seen, this vessel is in efficient condition &  
able in my opinion to remain as classed with record of survey,  
when the new bower anchor has been examined & found in  
des

Fees (if chargeable) per Scale II., Sec. 27 £ : : Fees applied for, 14/12/ 1894  
y Fee (per Section 28) £ : : Received by me, 15 12 94  
l Damage or Repair Fee (if any) £ 3 : 3 : 0  
ling Expenses (if chargeable) £ : : AKD 17  
d Surveyor's Fee (if any) £ : :  
ertificate now required?  
nmittee's Minute TUES. 18 DEC 1894 FRIDAY 18 JAN 1895  
aracter assigned White Ouzy 90A1  
Ar. 19.12.94. See Muz. No. 31203  
Lloyd's Register Foundation  
LON704 0057