

on from her present voyage.

This Special Survey, the following
examination of the vessel has yet to be held
of which the owner's representative has been
advised.

1. A strake of deck next waterways on each side
to be removed, it should be observed that the
owners contemplate renewing the main deck.
2. All the outside planking from light water
mark upwards including covering boards &
waterways to be scraped or dubbed bright.
3. Two planks in topsides on each side above
wales, also a plank in each bow and
buttock to be removed & timbers examined.
4. All the treenails in one strake of topside
planking to be removed on each side
and timbers tested.
5. The Raised Quarter deck, beams, ceiling
& in cabins aft to be examined.
6. The Windlass to be unhung and the
liveries to be partly removed.
7. The pumps and the general equipment
to examine.
8. That the wood doubling, and sheathing
on bows need not be removed or the
treenails driven out as directed by
paragraphs 27 & 33 of Section 60 of the
Wood Rules, provided the vessel be again
examined in dry dock on her return to
London as proposed by the owners, and
such examination be made of the bottom
fastenings in way of this doubling and
sheathing, as may be deemed necessary
by the Society's Surveyors in accordance
with the Secretary's letter of the 11th Decr. 94.

Repairs now done:- A teak hog keelson 14" x 15" fitted, before the
foremast to abft the mizen mast, properly scarphed & bolted
the stanchions & beams refitted, & mast re-stepped and re-
wedged, tricing set up, the main mast & main topmast being
renewed. Two diagonal straps or riders fitted each
side at ^{the} ~~fore~~ end. The Rudder lifted & deck pintle
brace renewed & several seams of bottom near
bow caulked on each side. Edward M. Dierney.

100-005207
LON