

REPORT of SURVEY for REPAIRS, &c.

Date of writing Report. 30th Aug 1895 When handed in at Local Office.

18 Port of London

No. in Survey held at London Date, First Survey 6th Aug 1895 Last Survey 28th Aug 1895
eg. Book. 592 on the River, Iron or ship "Turakina" (No. of Visits) Master HamorTONNAGE: Built at Glasgow By whom C. Connell & Co When 1868 - 5
GROSS 1247
UNDER Dk. 1160
NET 1189
Owners New Zealand shipping co lim Port belonging to London
Owners' Address

Surveyed Afloat or in Dry Dock? Both Name of Dock London Graving Dk Destined Voyage Port Chalmers

WB=CellDBorDBa tons; uE&B tons; f tons; t tons; FPT tons; APT tons; MT tons.

Particulars of Classification (which must be inserted precisely as in Register Book & Supplements).

N.B.—All alterations in the existing records should be underlined.
If the vessel has Water Ballast Tanks, state whether the manhole covers have been removed, and the insides of the tanks examined. Also state the amount of deterioration (if any) found in the thicknesses of the floors, framing, girders, and of the inner bottom plating, especially in the boiler space.

CHARACTER.	Years Assigned now expired.	Machinery and Boiler Surveys (including date of N.B., if any).
X for Special Survey.		
Date of last Survey and of Periodical Surveys.		
A 11.94		

S.S. Ddn N°3-1.83

S.S. Ddn N°2-91 ✓

Society's Freeboard (if assigned) as painted on Ship and now verified | 4 ft 5 1/2 ins.

Last Survey, No. 3051 Port Ham

(Periodical Surveys, when held, must be reported in detail and serially in the terms of the Rules. State clearly the cause of Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; and besides being detailed in the body of the report, should be summarised in the form shown below. Whenever the replacement of Anchors, Chains, or Hawser is reported, the particulars of weight or size and test of the articles should be clearly stated, and also the weight or size, &c., required by the Rules, together with the vessel's Equipment Letter, if any. State also the dates and initials of any letters respecting this case.)

REPAIRS, OR EXAMINATION AS PER RULE, FOR Part Second Special Survey N° 3

Now done:— Vessel placed in dry dock outside channel, examined and found in good condition.

Insulation of refrigerating chamber removed in accordance with the Secretary's letter "21.7th August 1895," and plating frames be at this part examined and found in good condition: Shell plating drilled and thickness found satisfactory (see sketch attached hereto): Fore and after peaks cleared, all oxidation removed from plating frames be in same; peaks decks, slices Masts (wedges removed) spars, chain cables (ranged) windlass and general equipment examined and found or put in good condition.

Repairs done on account of Wear & Tear:— Fore upper topail yard renewed rigging overhauled and renewed where necessary, on brasthook refastened

To complete this survey the following requires to be done:— all close ceiling at fore and after ends of hold removed, all floors, frames shell plating

SUMMARY OF DAMAGE REPAIRS:—	Plates.	Frames.	R. Frames.	Floors.	Beams.	Other Items:—
Renewed	✓	✓	✓	✓	✓	
Faired or Repaired ...	✓	✓	✓	✓	✓	

PRESENT CONDITION OF THE	Timbers of Frame at the openings	Good	Rudder	Good	Hatches	Good
Beams	ditto at other places	"	Windlass & Capstan	"	Boats	"
Keelsons		"	Pumps	not tested	Masts, Yards, &c.	"
Clamps, Shelves & Stringers		"	Sluice Valves	good	Condition, how ascertained by examination (State if wedges removed)	yes
Salting (State if examined.)	—		Watertight Doors	—	Sails	good
Ceiling	"		Dblng. Plates under Sounding Pipes	good	Equipment letter	
Cement or Asphalt (State which.)	none		Engine Room Skylights	"	Anchors, No. of	3B-15-2K
Tanks (State if now tested.)			Cooler Bunker, Open'gs, Lids, &c.	"	Cables (State if now ranged)	yes
Caulking of Bot'm, D'k, & Wat'rwy's	"		Scuppers	"	" length 300 size 1 1/2 - 2 1/2	
Copper, or Y.M. (State if on Felt.)	✓	✓	Cargo & Main H'tchwy's	"	" Rule length 270 size 1 1/2	
When put on, Month Year					Hawsers & Warps	sufficient
Transoms, Pointers, & Critches	"				Standing & Running Rigging	good

General Observations, Opinion as to Class, Recommendation, &c.:—

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:—".....to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey, 9,91," or "to remain as classed and to have record of survey, 9,91, and the notations of No. 1-91 and ptND91, &c."

This vessel as far as seen is in a good and efficient condition and eligible in our opinion to remain as classed and to have record of survey 8.95 and the notation of 2nd S.S. Lon N°3-8.95 when the survey has been completed.

Fees applied for,
2.9. 18
Received by me,
11/09/95
ACJ

W. Morrison
Surveyor to Lloyd's Register of British & Foreign Shipping
FRI. SEP 25 1896

Committee's Minute

TUES. 3 SEP 1895

Character assigned Deferred for consideration of No. 3
M.W.3

LON706-0291 1/2

Lloyd's Register
Foundation

Port of

Continuation of Report No. 56894 dated MON. 2 SEP 1895 on the

Iron ship "Turakina"

shell plating, beams, cement &c at this part examined in accordance with the Rules : peak bulkheads to examine on both sides; poop side plating to drill for thickness in way of side lights^{and chain plates}; and hand pumps to test.

It is the Owners intention to complete the survey on the vessel's return from her present voyage.

WM