

REPORT of SURVEY for REPAIRS, &c.

Survey Report 6 Feb. 1897 When handed in at Local Office

Port of London

Date, First Survey Jan 21st Last Survey 3 Feb. 1897

(No. of Visits 6)

Master Mayoso

YEAR

MONTH

NNAE: Built at Glasgow. By whom J. Elder & Co. When 1883 8

Owners New Zealand Shipping Co. Port belonging to London

Owners' Address

(if not already recorded in Appendix to Register Book.)

yed Afloat or in Dry Dock? Name of Dock aches dry dock. Destined Voyage New Zealand.

Cell DBor DBa feet; uE&B feet; f feet; t tons; FPT tons; APT tons; MT feet tons.

Particulars of Classification (which must be inserted precisely as in Register Book & Supplements).

B.—All alterations in the existing records should be underlined.

the vessel has Water Ballast Tanks, state whether the manhole covers have been removed, and the insides examined. Also state the amount of deterioration (if any) found in the thicknesses of the floors, framing, and of the inner bottom plating, especially in the boiler space.

Survey, No. 58069a Port London

al Surveys, when held, must be reported in detail and seriatim in the terms of the Rules. State clearly the Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; details being detailed in the body of the report, should be summarised in the form shown below. Whenever the ment of Anchors, Chains, or Hawser is reported, the particulars of weight or size and test of the articles be clearly stated, and also the weight or size, &c., required by the Rules, together with the vessel's Equipment if any. State also the dates and initials of any letters respecting this case.

S, OR EXAMINATION AS PER RULE, FOR Park Special Survey h^o 3.

Vessel placed in dry dock bottom examined cleaned & painted. Rudder lifted and pintles rebrushed.

The fore and after peaks examined scaled and painted

The liner boards on each side of centre keelson No. 3 were lifted the liners cleaned out and cement & chisel in way of same examined.

The fish side of the boiler space cleared out from the keelson to lower bilge keelson and examined. This space is closed in with solid cement extending above the reverse frames, about for a short length on each side of the ^{centre} keelson. The reverse frames and keelson angles are somewhat wasted in this part & the owners propose to deal with this and complete the h^o 3 on the vessel's return in about 4 months time as approved by Secretary's letter (S) of 30th January, and 1st February.

OF DAMAGE REPAIRS:— Plates. Frames. R. Frames. Floors. Beams. Str. Plates. Dk. Plates. Other Items:—

Renewed ...

Fair'd or Repaired ...

CONDITION OF THE	Timbers of Frame at the openings	Rudder	Hatches
Good	Good	Good	Good
"	ditto at other places as above	"	"
Keelsons	" "	Windlass & Capstan	Masts, Yards, &c.
Stringers, Gamps & Shelfs	Good	Have Pumps now been examined and found efficient? Yes in Peaks.	Condition, how ascertained From DR.
Salting	(State if present.)	Have Sluice Valves now been examined and found efficient? Yes in Peaks.	(State if wedges removed)
Ceiling	Part seen "	Have Watertight Doors now been examined and found efficient?	Sails.
Cement or Asphalt	(State which.)	Dblg. Plates under Sounding Pipes	Equipment letter X.
Tanks	"	Engine Room Skylights	Anchors, No. of 4 B. 15. 2 K.
(State if now tested.)		Coal Bunker, Open'gs, Lids, &c.	Cables (State if now ranged) True.
Caulking of Bot'm, D'k, & Wat'rwy's.	"	Scuppers	" length (on board) size.
Copper, or Y.M.	(State if on Felt.)	Cargo & Main H'tchw'y's	" Rule length (per Table 22) size.
Spars, & Crutches	When put on, Month Year		Hawsers & Warps Good
			Standing & Running Rigging "

al Observations, Opinion as to Class, Recommendation, &c.:—

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon survey, thus, for example:—"to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey, 9,91," or "to remain as classed and to have record of survey, 9,91, and the notations of ss No. 1-91 and ptND91, &c."

This vessel, is eligible in my opinion to remain as classed for the voyage without fresh record of survey.

chargeable per Scale II, Sec. 27	£	:	;	Fees applied for,
per Section 28)	£	:	:	18
ge or Repair Fee (if any)	£	:	:	
enses (if chargeable)	£	:	:	18
or's Fee (if any)	£	:	:	

Received by me,


E. B. Charnress
Surveyor to Lloyd's Register of British & Foreign Shipping.

Is Certificate required? If so to be sent to

tee's Minute TUES 9 FEB 1897

er assigned Deferred for
couple. of Mo. 3.FRI. 9 JUL 1897
TUES. 14 DEC 1897

FRI. 29 OCT 1897



© 2019 FRIDAY 26 MAY 1898

Port of

London

Continuation of Report No. 584,91 dated 6.2.97 on the

Steel S.S. "Tongariro"

To complete the S.S. h^o3 the following remains to be done

1. The close ceiling in h^o3 hold to be lifted and cement and steelwork in way of same to be examined.
2. The reverse frames, lower deck stinger and lower deck beams in the side bunkers abreast of h^o3 hold to be repaired.
3. The vessel to be examined in way of sidelight in saloon and rooms aft.
4. The vessel ^{as far as} cleaned out under engine and boilers for examination and the reverse frames and keelson angles in boiler space repaired.

E.B. Charnress